

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

For corners in **Fremont Twp.**
TUSCOLA
(County)

Located In:

Corner Code #

1. Public Land Survey	T	11N	R	09E	E-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 71
FREMONT TWP.
94 OCT 10 AM 8:49
VIRGINIA M. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 14 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET POST; SUGAR 17 N22W 24LKS., HEMLOCK 9 N59E 35LKS.
1891 FELTON, C.S.; FROM MEAS. NO OBJECT STATED; ELM 4 N67E 73LKS., BITTERNUT 5 N78W 162LKS.
1891 FELTON, C.S.; SET FROM MEAS. STONE 14" LONG & CROCKERY; SAME WITS AS 1891 ABOVE
1976 KAY ENG.; KAY, P.S.#14096; SURVEY L.449, PG.536-537; 5/8" ROD; SOUTH 17.42' W LEG RD SIGN S40°W 26.67' 10" BASSWOOD, N45°W 45.30' RD SIGN POST
1988 ROWE ENG.; WIT CARD; TUSCOLA CO. RD COMM. WITS; 1/2" IRON BAR; S65°W 64.00' NAIL TWIN 8" ASH, S30°E 54.75' NAIL 4" ASH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" SMOOTH ROD 1.5'S. & 3.5'W. OF C/L - C/L OF GRAVEL ROADS E-W-N 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1976 KAY ENG. IRON
ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-13 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)
N14°E, 144.34' SET NAIL W/REMON TAG IN W. FACE P. POLE
N49°E, 53.52' TOP CENTER OF PHONE RISER
SOUTH, 17.42' W. EDGE OF W. SIGN POST LEG
S46°W, 26.92' SET NAIL W/REMON TAG IN NW FACE 14" BASSWOOD
S59°W, 63.96' SET NAIL W/REMON TAG ABOVE FND NAIL W/FLAG IN N. FACE 10" ASH
N79°W, 102.96' SET NAIL W/REMON TAG IN N. FACE 40" ASH
N19°W, 52.2' CENTER OF ROAD SIGN POST

Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
E-29-94
J.M.F.



