

SURVEY & REMONUMENTATION

OCT 20 1994

COMMISSION

For corners in **Fremont Twp.**
TUSCOLA
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
1994 REMONUMENTATION PROGRAM

Located In:

Corner Code #

- 1. Public Land Survey T 11N R 09E
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

F-13

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILMS NO. # 72
REMON TWP
94 OCT 10 AM 8:49
VIRGINIA M. MCCLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, **JONATHAN M. FIELD**, in a field survey on **JULY 14** 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 GLO; PARKE, D.S.; SET POST; SUGAR 24 N62W 22LKS., SUGAR 11 N73 1/2E 18 1/2LKS.
 - 1891 FELTON, C.S.; SET FROM B.T.'S IN 1875 CEDAR POST & CROCKERY; NO WITS GIVEN
 - 1975 KAY ENG.; KAY, P.S.#14096; SURVEY L.449, PG.536-537; 5/8" ROD; S10°E 28.38' 30" MAPLE, S15°W 44.20' 36" MAPLE, N15°E 30.90' 18" MAPLE
 - 1976 TOMMER, P.S.#22444; LCRC 34; FND 1/2" ROD N35°W 43.10' RD SIGN POST, SOUTH, 17.55' W LEG SIGN POST
 - 1978 BECK-GRAVLIN; BECK, P.S.#21559; SURVEY L.490, PG.251; 5/8" ROD; SAME WITS AS 1975 KAY ENG. SURVEY

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" SMOOTH ROD AT C/L GRAVEL ROAD E-W & ON LINE WITH FENCE TO N. 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1975 KAY ENG. IRON

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-13 REMOVED ROD, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC.)
 - S16°E, 29.18' SET NAIL W/REMON TAG IN NE FACE 30" MAPLE
 - S20°W, 45.54' SET NAIL W/REMON TAG IN NW FACE 30" MAPLE
 - N57°E, 44.42' SET NAIL W/REMON TAG IN N. FACE TWIN 6" ELM
 - N54°W, 24.94' SET 1/2" ROD



Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
8-29-94

J.M.F.

LEIX ROAD

SW 1/4
SEC 33
TIIN-R9E

SE 1/4
SEC 33
TIIN-R9E

CONRAD ROAD



180°00'20"

1834 GLO 2640'
1891 FELTON 2637.36'
1975 KAY 2643.0'
1994 REI 2641.22'

180°06'09"

1834 GLO 2640'
1891 FELTON 2641.32'
1978 BECK 2652.79'
1994 REI 2652.84'

E-13

F-13

G-13

BROWN ROAD