

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

COMMISSION

For corners in Fremont Twp.
TUSCOLA
(County)

Located In:

Corner Code #

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #73
REMONUMENT TWP.
94 OCT 10 AM 8:49
VIRGINIA H. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T 11N R 09E	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 14 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET POST; BEECH 8 N22E 20LKS., BEECH 9 N74W 25LKS.
1891 FELTON, C.S.; SET FROM MEAS. STONE 14" LONG & CROCKERY; PINE 6 N5 1/2W 186LKS., APPLE 6 N44E 109LKS.
1978 BECK-GRAVLIN; BECK, P.S.#21559; SURVEY L.490, PG.251; SET 1/2" IRON OVER IRON POST; N40°W 73.75' NAIL T. POLE, S60°E 81.14' IRON POST, S05°W 32.2' E LEG RD SIGN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD OVER T-BAR FENCE POST 2.5' S. OF C/L - C/L OF ASPH. ROADS E-W-N 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1978 BECK-GRAVLIN IRON

ACCEPTED 1/2" ROD AND FENCE POST AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 REMOVED ROD, CAST IN CONC. 5/8" ROD W/ STANDARD BRASS CAP OVER T-BAR FENCE POST IN MON. BOX

- S27°E, 36.11' CENTER OF GAS VENT PIPE
- S09°W, 32.58' E. EDGE OF E. SIGN POST LEG
- N76°W, 113.20' CENTER OF GAS VENT PIPE
- N31°W, 74.22' TOP CENTER OF PHONE RISER
- N40°E, 52.55' SET 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 9-2-94

Surveyor's Michigan License No. 37276

APPROVED
E-29-94

Handwritten initials and signature.

