

OCT 20 1994

COMMIS...

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

For corners in **Fremont Twp.**
TUSCOLA
(County)

Located In:

Corner Code #

COPY

94 OCT 10 AM 8:50
Fremont Twp.
VIRGINIA M. McLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 75

Register of Deeds Stamp & File Number

1. Public Land Survey	T	11N	R	09E	I-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 14 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:
 1834 GLO; PARKE, D.S.; SET POST; B.ASH 18 N22E 10LKS., B.ASH 15 N85W 17LKS.
 1962 R.J. BLACK, P.S.#3384; WIT CARD AT ROWE ENG.; FND 5/8"X 30" IRON; S75°W 105.60' NAIL 12" ASH, N75°W, 126.95' NAIL 12" MAPLE, SOUTH 19.10' RD SIGN, N45°W 57.60' NAIL GUARD POST
 1981 DUNTON SURVEYING; DUNTON, P.S.#23503; SURVEY L.522, PG.1053; 1/2" ROD OVER 1" SQ. IRON; S30°E 45.7' P-K IN FE POST, S30°W 45.6' P-K IN FE POST, SOUTH 3.8' C/L PVMT.
 1981 DUNTON, P.S.#23510; LCRC 47; 1/2" ROD OVER 1" SQ. ROD; WITS SAME AS 1981 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD OVER 1" SQUARE ROD 2' E. OF C/L EXT. MERTZ ROAD (ASPH.) N., 4' N. OF C/L ASPH. RD. E-W 1 PREVIOUS WITNESS INDICATES THAT 1/2" ROD IS IN SAME POSITION AS 1962 BLACK IRON

ACCEPTED 1/2" ROD & 1" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-13 REMOVED 1/2" ROD, CAST IN CONC. STANDARD BRASS CAP W/ 5/8" ROD OVER 1" ROD, IN MON. BOX)
 N44°E, 21.69' SET 1/2" ROD
 S71°E, 106.99' SET NAIL W/REMON TAG IN N. FACE FENCE POST
 S36°W, 24.56' E. EDGE OF E. SIGN POST LEG
 N76°W, 127.14' SET NAIL W/REMON TAG IN S. FACE 20" MAPLE
 N15°W, 135.99' SET NAIL W/REMON TAG IN E. FACE T. POLE



Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
8-29-94
J.M.F.

