

OCT 20 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 REMONUMENTATION PROGRAM

For corners in Fremont Twp.
TUSCOLA
(County)

Located In:

Corner Code #

COPY

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 76
FREMONT TWP.
94 OCT 10 AM 8:50
VIRGINIA M. McLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

1. Public Land Survey	T 11N R 09E	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 14 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1834 GLO; PARKE, D.S.; SET POST; B.ASH 10 NO BEARING OR DIST., B.ASH 9 N20E 101KS.
 1970 ROWE ENG.; SURVEY NOTES JOB NO. C-0074-70; SET RR SPIKE ON OCCUPIED N-S FENCE LINE; NO WITS GIVEN
 1973 ROWE, P.S.#11192; LCRC 24; SET RR SPIKE ON OCC FE LINE N-S & ON LINE BTWN L-13, T11N-R9E & K-1, T10N-R9E; N70°W 128.95' NAIL P. POLE, N75°E 96.62' N END 18" CMP, S75°E 94.39' S END 18" CMP
 1981 DUNTON SURVEYING; DUNTON, P.S.#23503; SURVEY L.522, PG.1053; 1/2" ROD; EAST 91.5' CSP, N50°W 30.2' N LEG SIGN POST, NW 190.00' 1/2" ROD W/CAP #23503
 1981 DUNTON, P.S.#23503; LCRC 47; 1/2" ROD; SAME WITS AS 1981 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ROWE ENG. - FIELD, P.S.#37276; FND 1/2" ROD ABOVE REMNANTS OF WOOD POST AT C/L ASPH. ROAD E-W 2 PREVIOUS WITNESSES INDICATE THAT 1/2" ROD IS IN SAME POSITION AS 1973 ROWE ENG. IRON
 ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

SEE ALSO BACK OF THIS FORM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-13 REMOVED ROD AND PORTION OF WOOD POST, SET STANDARD MONUMENT (5/8"X36" ROD W/ BRASS CAP IN CONC., IN MON. BOX)
 N68°W, 132.77' SET NAIL W/REMON TAG IN S. FACE P. POLE
 S55°W, 26.58' SET 1/2" ROD
 N76°E, 97.29' SET CHIS. NOTCH IN TOP N. END 18" CSP
 S76°E, 92.69' SET CHIS. NOTCH IN TOP S. END 18" CSP



Signed by Jonathan M. Field Date 9-2-94
Surveyor's Michigan License No. 37276

APPROVED
E-29-94

Handwritten initials and signature.



MERTZ ROAD

SW 1/4
SEC 35
TIIN-R9E

SE 1/4
SEC 35
TIIN-R9E

180°07'24"

179°34'50"

1834 GLO 2640'
1994 REI 2642.03'

1834 GLO 2640'
1994 REI 2642.39'

I-13

J-13

K-13

BROWN ROAD

