

SURVEY & RECORDS

OCT 20 1994

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in DAYTON TOWNSHIP

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #57
DAYTON TWP
94 OCT -4 AM 10:33
VIRGINIA H. HOLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

TUSCOLA (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R10E	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Lionel Roy Emery in a field survey on May 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S. -set quarter section post- Hemlock 18 N27W 42; Beech 18 N88E 6 1/2
 - 1987 (Survey -Liber 573, pages 1497 and 1498) Russell L. Brown, P.S. #24588- set 1" Pipe by single proportion measurement from found markers at S.E. and S.W. corners of Section 36. West, 156.63' nail S. side of P.P.; N05°W 18.44' nail W. side P.P.; N30°W 6.46' Guy Wire Anchor
 - 1991 (Survey -Liber 618, pages 421 and 422) Earl E. Gravlin, P.S. #23510 -Found 2" Shaft- N05°W 18.50' P. Pole (also 1/2" rerod); N80°W 156.55' P. Pole

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 1" Pipe with half of union fitted to top
 - Accepted 1" Pipe as marking original corner

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Removed Pipe and replaced with Standard Tuscola County Concrete Monument w/ 2" Brass Cap stamped L13 T11N R11E
 - S50°E, 26.02' - set 1/2" iron rerod in approximate centerline of abandoned Marlette Road
 - S60°W, 24.95' - set 1/2" iron rerod in approximate centerline of abandoned Marlette Road
 - N80°W, 156.54' - T.C. Remon. tag over found nail in S.W. face of power pole
 - N08°W, 18.48' - T.C. Remon. tag over found nail in West face of power pole (fnd 1/2" rerod @ base)
 - North, 1.0' - Fiberglass "Survey Marker" witness post

Signed by Lionel Roy Emery
Surveyor's Michigan License No. 24593

Date October 4, 1994

APPROVED
8-9-94



