

1996 REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dayton Twp.

Tuscola Located In: Corner Code #  
 (County)

1. Public Land Survey T11N R10E M-12  
 T R  
 T11N R11E A-12  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

RECEIVED FOR RECORD  
 LIBER NO. PAGE NO. 80  
 FILE NO. Dayton  
 96 DEC 10 PM 4:50  
*John A. Teskey*  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kenneth D. Dunton in a field survey on May 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1834 August 23, 1882  
 Harvey Parke, D.S. John A. Teskey, County Surveyor  
 Set Quarter Sec. Post Sec. 31 T11N-R11E  
 Hemlock 22 N28W 47 Stake previously set  
 Beech 5 S10 1/2W 31 Perpetuated by stake  
 No accessories

Note: Section A continued on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod (bent). Held as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Removed 1/2" rod and set standard monument stamped Corner M-12, T11N-R10E.  
 S14°W 107.33' set T. C. Remon. tag & spike in NW face T. pole stub.  
 S89°W 136.96' set T. C. Remon. tag & spike in S. face P. pole.  
 S88°E 33.20' set T. C. Remon. tag & spike in N. face P. pole.  
 S76°E 26.42' chiseled notch atop E. end 12" CSP.

Note: This corner is common with A-12, T11N-R11E.

Signed by *Kenneth D. Dunton*  
 Surveyor's Michigan License No. 23503

Date \_\_\_\_\_

APPROVED  
11-11-96  
*[Signatures]*



Aug. 4, 1977

Survey by Robert G. Kay, Land Surveyor #14096, Liber 476-Pages 948 & 949.  
1/2" iron.

S20°W 107.15' nail T.P. riser.

West 26.80' nail fence post.

East 21.40' nail fence post.

May 7, 1991

Survey by John A. Milletics, Land Surveyor #25859, Liber 614-Page 1000.  
No mention of object found or set or accessories.

