

Survey & Remonumentation

COPY

OCT 20 1994

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Koylton Township

TUSCOLA (County)

Located In:

Corner Code #:

- 1. Public Land Survey T 11N R 11E G-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED FOR RECORD
LIBER NO. - PAGE NO.
FILING NO. # 23
KOYLTON
94 AUG 19 AM 11:12
VIRGINIA H. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kenneth D. Dunton in a field survey on May 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. Notes
Harvey Parke, D.S.
Set post corner
Sections 33 & 34
Cedar 12" N75 1/2°W 34 links
Cedar 9" N75°E 19 links

1957-59 M.S.H.D. road plans
Project No. 44081 & 74041, sheet 8
P.I. Sta. 241+90.20. 1" pipe
N68°W 63.96' tele. p.
S27°E 58.78' p.p.
N74°E 80.71' tele. p.

Witness card
No date
Delamater-Muschell
Engr. & Land Surveyors
Cheboygan, MI
Same witnesses & object
as 1957-59
M.S.H.D. plans

Section A continued on back of this form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in monument box and accepted as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed boat spike and replaced with 18" x 5/8" rod & 2" standard brass cap in concrete. Stamped cap G-13, T11N-R11E.
N47°43'W 58.15' chiseled "+" atop center of concrete headwall.
N52°20'E 44.80' chiseled "+" atop center of concrete headwall.
S28°11'E 58.80' found M.S.H.D. tag in NE face p. pole. Also found p.k. nail & 2" disk in SW face at 59.10'.
S35°07'W 50.56' set T.C. Remon. tag & spike in NW face 15" pine. Also remains of 2" disk at 50.62'.

Signed by [Signature]

Date Aug. 1, 1994

Surveyor's Michigan License No. 23503

APPROVED

8-1-94



COPY

Section A continued:

May 19, 1982 Lapeer County Road Commission, Marlette Road corner witnesses, sheet 2 of 4.
Found boat spike in monument box.
S45°E 59.12' set p. k. nail w/flasher in D. E. pole.
S45°W 50.85' set p. k. nail w/flasher in 9" scotch pine.
N45°E 51.51' set p. k. nail w/flasher in fence post.

