

COPY

DEC 07 1994

COMMISSION

1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KOYLTON TOWNSHIP

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #39
KOYLTON TWP.
94 NOV -9 PM 2:20
VIRGINIA H. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

TUSCOLA (County)	Located In:	Corner Code #/
1. Public Land Survey	T 11N R 11E	M-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Lionel Roy Emery, in a field survey on June 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S. -Set quarter section post- B. Ash 12 S4W 43; Hemlock 10 N34W 43
- 1972 (Survey -Liber 1 of Surveys, page 349) David T. Rowe, P.S. 11192 -set "T" iron- N45°E 15.1 PK nail in 4" tree; East 33.0' "T" iron; S80°W 30.56' PK nail in Anchor post; West 33.0' "T" iron
- 1972 (Survey -Liber 2 of Surveys, pages 20 and 21) David T. Rowe, P.S. 11192 - same marker and accessories as above Survey except distance to "T" iron East shows as 23.0'
- 1972 (Land Corner Recordation Certificate) David T. Rowe, P.S. 11192 -Found pieces of wood & charcoal 1.5'+/- under rd. Raised with "T" Iron. Accessories same as shown in 1972 Survey- above-- Liber 1 of Surveys, page 349.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron; found no accessories remaining; found remains of fence corner post and braces East side of road.
Accepted found "T" iron as marking original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Removed "T" iron and replaced with Standard Tuscola County Concrete Monument w/ 2" Brass Cap stamped M10 T11N / R11E
- N65°E, 45.15' T.C. Remon. tag in NW face of 9" Apple tree
- S65°E, 25.60' T.C. Remon. tag in SW face of 2" Ash
- S40°W, 17.11' Set 5/8" diameter reinforcing rod
- N40°W, 14.87' Set 5/8" diameter reinforcing rod



Signed by Lionel Roy Emery Date Aug. 31, 1994
Surveyor's Michigan License No. 24593

APPROVED
8-31-94

COPY

