

1995 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Denmark Township

Tuscola (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORDS
LIBER NO. _____ PAGE NO. _____
FILING NO. # 63
DENMARK TWP.
95 NOV -9 PM 3:37
VIRGINIA H. McLANE
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton, in a field survey on August 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes
Orange Risdon, D.S.
Set Post Corner of Sections 32 & 33
Beech 10" N75E 61 Links
Lynn 12" N37W 73 Links
Lynn 24" N8E 7 Links

June 26, 1971 Act 74 Form filed by David T. Rowe, R.L.S. #11192, Page 23, Denmark Township. Set "T" iron. N50°W 22.57' nail in p.p., N20°E 96.94' SW cor. gar. #8944, North 3.5' physical centerline E-W pavement.
June 28, 1971 Survey by David T. Rowe, R.L.S. #11192, recorded in Liber 1 Page 158, Tuscola County Records. Same witnesses as Act 74 Form, Page 23 Denmark Twp.
September 26, 1978 Survey by David T. Rowe R.L.S. #11192, recorded in Liber 491 Page 981 Tuscola County Records. Same witnesses as Act 74 Form, Page 23 Denmark Twp.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron, also found 3/4" pipe over iron bar 6.35' Northwest. Found no other evidence below irons. Accepted "T" iron as the proper position of Corner E-13. The "T" iron falls proportional to the G.L.O. notes relative to adjacent Corners C-13, D-13, F-13 & G-13 along the township line.

DEC 1 1995
COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed "T" iron and placed concrete monument with standard brass cap stamped Corner E-13, T12N-R7E. Placed monument box over monument.

S51°24'E 15.10' center of 3" pipe (mail box post).
S61°47'W 20.33' set 1/2" x 18" re-rod in road shoulder.
N06°59'W 23.05' set T. C. Remon. tag & spike in East face p. pole. (Fnd. nail & #11192 tag in S. face @ 22.74').
N19°53'E 44.03' set T. C. Remon. tag & spike in West root 15" maple.
N47°24'W 6.35' fnd. 3/4" pipe.
N17°50'E 96.95' SW corner brick garage at #8944.
North 3.5' physical centerline E-W pavement.

Signed by [Signature] Date 10-23-95
Surveyor's Michigan License No. 23503

APPROVED
10-23-95

KENNETH D. DUNTON
LAND SURVEYOR
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

