

1995 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Denmark Township

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
 FILING NO. H 64  
DEM MARK TWP.  
 95 NOV -9 PM 3:37  
 VIRGINIA H. McLAUREN  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton, in a field survey on August 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes  
 Orange Risdon, D.S.  
 Set 1/4 Section Post  
 Beech 18" North 29 Links  
 White Oak 28" N80E 63 Links

June 28, 1971 Survey by David T. Rowe, R.L.S. #11192, recorded in Liber 1 Page 158, Tuscola County Records. 1" pipe. N50°W 132.47' nail in p.p. North 3.5' centerline pavement, N80°E 200.89' nail in p.p.  
 June 26, 1971 Act 74 Form filed by David T. Rowe, R.L.S. #11192. Witnesses and accessories the same as Survey Liber 1 Page 158.  
 September 26, 1978 Survey by David T. Rowe, R.L.S. #11192. Recorded in Liber 491 Page 981 Tuscola County Records. 1" pipe. North 3.5' centerline pavement, North 19.40' angle iron, S50°W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

38.30' N. end of 4" field drain tile.

Found 1 1/4" iron bar. Accepted evidence found as the proper position of Corner F-13.

CLAWAY &  
 SURVEYORS & ENGINEERS

DEC 6 1995

COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1 1/4" x 30" iron bar, also quantities of glazed tile, white pottery, crockery & 3 1/2" diam. red glazed jug and placed concrete monument with standard brass cap stamped Corner F-13, T12N-R7E. Placed monument box over monument.

N02°42'E 19.35' steel fence post in place.  
 North 3.5' physical centerline of E-W pavement.  
 S45°25'E 13.90' set 1/2" x 18" re-rod in road shoulder.  
 N44°35'W 13.55' set 1/2" x 18" re-rod in road shoulder.  
 N45°25'W 24.32' set 1/2" x 18" re-rod in road shoulder.  
 N44°35'E 25.36' set 1/2" x 18" re-rod in road shoulder.

Signed by [Signature] Date 10-23-95

Surveyor's Michigan License No. 23503

APPROVED  
10-23-95  
 [Signature]



