

1995 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. _____
 FILING NO. # 105
 DENMARK TWP
 95 NOV -9 PM 3:37
 VIRGINIA M. McLAREN
 TUSCOLA COUNTY
 REGISTER OF DEEDS

For corners in Denmark Township

<u>Tuscola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on August 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes
 Orange Risdon, D.S.
 Set Post Corner of Sections 33 & 34
 Black Ash 12" N42E 32 Links
 Elm 10" N69W 25 Links

May 4, 1971 Act 74 Form filed Page 22 Denmark Township by David T. Rowe, R.L.S. #11192. Found spike in asphalt. N75°W 107.62' nail in p.p., N70°E 53.64' SE cor. concrete hdwl., S80°W 148.39' nail in 24" oak.
 May 9, 1978 Act 74 Form filed by Ronald C. Prevost R.L.S. #24612. Set 3/4" iron bar in place of nail found. S85°E 44.60' S.E. cor. S. hdwl. culvert, S60°E 41.20' N.W. corner W. hdwl. bridge, N45°E 47.22' N.W. cor. E. hdwl. bridge.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" iron bar 24" long. Accepted evidence found as the proper position of Corner G-13.

SURVEY &
 RECORDATION
 DIVISION
 DEC 1 1995
 COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed iron bar and placed concrete monument with standard brass cap stamped Corner G-13, T12N-R7E. Placed monument box over monument.

S55°41'E 41.25' West corner, Southwest concrete headwall.
 N51°56'E 47.25' North corner, Northeast concrete headwall.
 S33°39'W 39.50' found 2" pipe.
 N77°09'W 111.83' set T. C. Remon. tag & spike in NE face p. pole.
 N29°19'E 20.7' physical centerline State Highway M-15.

Signed by [Signature]

Date 10-23-95

Surveyor's Michigan License No. 23503

APPROVED
10-23-95
 [Signature]



