

1995 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Denmark Township

Tuscola \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code H-13  
 (County)

1. Public Land Survey	T <u>12N</u> R <u>7E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
 LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
 FILING NO. # 166  
 DEN/MAK TWP.  
 95 NOV -9 PM 3:37  
 VIRGINIA H. McLAUREN  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth D. Dunton, in a field survey on August 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes  
 Orange Risdon, D.S.  
 Set 1/4 Section Post  
 Black Oak 36" N70E 48 Links  
 Birch 12" North 7 Links

\* May 5, 1980 - See back of this certificate.  
 March 22, 1982 Survey by Kenneth D. Dunton, R.L.S. #23503 recorded in Liber 525 Page 820, Tuscola County Records. No mention of object found, set or accessories.  
 March 22, 1982 K. D. Dunton, R.L.S. #23503 field notes Job #151-82 found nothing set R.R. spike - chiseled "+" on top - set by single proportion measure on line between SW & SE corners of Section 34. N60°W 80.10' p.k. in p.p., N02°E 46.95' p.k. in p.p., N40°E 72.57' p.k. in p.p., North 1' ± centerline pavement.

Section A continued on back of this form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike with "+" chiseled atop. Accepted evidence found as the proper position of Corner H-13.

SURVEY &  
 RECONSTRUCTION  
 DEC 1 1995  
 COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed R.R. spike and placed concrete monument with standard brass cap stamped Corner H-13, T12N-R7E. Placed monument box over monument.

S00°27'E 13.70' set 1/2" x 18" re-rod in road shoulder.  
 N63°54'W 80.09' set T. C. Remon. tag & spike over P. K. nail found in South face p. pole.  
 N33°35'W 53.72' set T. C. Remon. tag & spike in SW face p. pole.  
 N03°42'E 46.93' set T. C. Remon. tag & spike over P. K. nail found in East face p. pole.  
 N39°23'E 72.55' set T. C. Remon. tag & spike over P. K. nail found in SW face p. pole.

Signed by [Signature] Date 10-23

Surveyor's Michigan License No. 23503

**APPROVED**  
10-23-95  
 [Signatures]

KENNETH D. DUNTON  
 LAND SURVEYOR  
 No. 23503

Section A continued:

\* May 5, 1980 Act 74 Form filed by Kenneth D. Dunton, R.L.S. #23503 on Page 52, Denmark Township.  
Set R.R. spike, chiseled "+" on top, set by single proportion measure, accessories the same  
as field notes for Job #151-82. Job #151-82 being recorded in Liber 525 on Pages 820 & 821.

