

1995 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
 LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
 FILING NO. # 68  
 DENVER TWP.  
 95 NOV -9 PM 3:37  
 VIRGINIA K. McLELLAN  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

For corners in Denmark Township

<u>Tuscola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kenneth D. Dunton, in a field survey on August 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes Orange Risdon, D.S. Set 1/4 Section Post to Sec. 35 White Oak 22" N46W 20 Links White Oak 18" N42E 48 Links	Nov. 26, 1979 Survey by Kenneth D. Dunton, R.L.S. #23503 recorded in Liber 508, Page 842, Tuscola County Records. Set 1/2" rod and cap by single proportion method. N02°E 156.67' p.k. nail in p.p., South 0.8' N. edge 20' wide pavement, NW 16.5' W. end conc. drive culvert, NE 27.8' E. end conc. drive culvert. May 8, 1980 Act 74 form by K. D. Dunton, R.L.S. #23503 Section A continued on back of this form. Filed on Page 51 Denmark Township. Data same as Survey Liber 508, Page 842.
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod & cap #23503 and accepted as the proper position of Corner J-13.

SURVEY &  
 MONUMENTATION  
 DEC 14 1995  
 COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed rod and placed concrete monument with standard brass cap stamped Corner J-13, T12N-R8E. Placed monument box over monument.  
 N48°21'W 16.52' chiseled notch atop W. end of 38' of 18" conc. drive culvert.  
 N67°03'E 27.73' chiseled notch atop E. end of 38' of 18" conc. drive culvert.  
 N00°45'E 156.59' placed T. C. Remon. tag & spike above P.K. nail found in W. face p. pole.  
 S00°42'E 26.00' set 1/2" x 18" re-rod on South shoulder of road.  
 South 1.1' North edge of newer 20' wide asphalt road edge.  
 South 0.3' North edge of old asphalt pavement below newer overlay.

Signed by [Signature]  
 Surveyor's Michigan License No. 23503

Date 10-23-95

APPROVED  
 10-23-95

[Signature]  
 J.M.I.  
 J.H.C.

STATE OF MICHIGAN  
 KENNETH D. DUNTON  
 LAND SURVEYOR  
 No. 23503  
 PROFESSIONAL  
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

Section A continued:

May 29, 1984 Survey by B. D. Ferguson, R.L.S. #26454 of Hammond Engineering, Liber 541, Page 1022 & 1023, Tuscola County Records.

No mention of object found or set or accessories.

