

1995 REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Denmark Township

<u>Tuscola</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 70
DENMARK TWP.
95 NOV -9 PM 3:37
VIRGINIA M. BELARIN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton, in a field survey on August 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Feb. 19, 1834 G.L.O. Notes
Orange Risdon, D.S.
Set 1/4 Section Post to Sec. 36.
Beech 6" N39E 25 Links
Beech 12" N24W 52 Links
Sugar 20" East 3 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of corner. Established by single proportion at split of measured mile and on line between corners K-13 and M-13, T12N-R7E.

SURVEY &
REMONUMENTATION

DEC 6 1995

COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed concrete monument with standard brass cap stamped Corner L-13, T12N-R7E. Placed monument box over monument.

N38°44'W 19.50' set 1/2" x 18" re-rod in road shoulder.
N26°49'E 17.29' set 1/2" x 18" re-rod in road shoulder.
S51°47'W 15.48' set 1/2" x 18" re-rod in road shoulder.
N64°09'E 62.50' chiseled notch atop W. end of 30' of 12" CSP culvert.
S62°16'E 50.26' set T. C. Remon. tag & spike in NE face p. pole.
North 2.5' physical centerline of E-W pavement.

Signed by [Signature] Date 10-23-95

Surveyor's Michigan License No. 23503

APPROVED
10-23-95



