

1995 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORDS
 LIBER NO. _____ PAGE NO. _____
 FILING NO. # 76
 DENMARK TWP
 95 NOV 21 PM 2:59
 VIRGINIA M. HELGREN
 TUSCOLA COUNTY
 REGISTER OF DEEDS

For corners in Denmark Township
Tuscola
(County)

	Located In:	Corner Code -#
1. Public Land Survey	T <u>12N</u> R <u>7E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on October 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. Notes Orange Risdon Set 1/4 Section Post Beech 12 S88W 14L Sugar 12 N13W 21L	June 4, 1990 Survey by Kenneth D. Dunton, L.S. #23503 recorded in Liber 608 Page 1137 & 1138, Tuscola County Records. Set R.R. spike in pavement by single proportion method. S70°E 39.7' center of 15" elm, S50°W 46.7' center of 15" maple, N50°W 62.3' center of 15" walnut, N01°39'29"E 2635.64' NE corner Sec. 13.
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike per Survey Liber 608, Page 1137 & 1138. Accepted spike as the proper location of Corner M-6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed railroad spike and placed concrete monument with standard brass cap stamped Corner M-6, T12N-R7E. Placed monument box over monument.
 S45°52'W 46.61' set T. C. Remon. tag & spike in SE face 18" maple.
 N53°48'W 61.70' set T. C. Remon. tag & spike in NE face 18" walnut.
 S72°04'E 39.40' set T. C. Remon. tag & spike in SW face 24" elm.
 N37°54'W 111.51' set T. C. Remon. tag & spike in East face p. pole.
 N37°55'E 26.45' set 1/2" x 18" re-rod in road shoulder.

Signed by [Signature] Date Nov. 14, 1995
 Surveyor's Michigan License No. 23503 APPROVED

11-14-95



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

DEG 1035
 COMMISSION

COPY



Section 13

T12N-R7E

1990 Dunton
180°00'00"

1995 Dunton
180°00'25"

1834 Risdon 2640'
1990 Dunton 2635.64'
1995 Dunton 2635.61'

M-7

1834 Risdon 2640'
1990 Dunton 2635.64'
1995 Dunton 2635.61'

M-5

Township Line

M-6

Section 18

T12N-R8E