

FEB 08 2001

SECTION

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #96 Juniata

For corners in: JUNIATA TWP.

Tuscola Located In:
(County)

Corner Code #

- 1. Public Land Survey T 12N R 8E K-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat
- 5. Private Claims

00 DEC 19 PM 1:34

Gregory M. ...
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kari M. Lohela, in a field survey on November 11, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4			3		2
3												
4	7						8			9		10
5												
6	18						17			16		15
7												
8	19						20			21		22
9												
10	30						29			28		27
11												
12	31						32			33		34
13												

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O. NOTES, ORANGE RISDON, D.S., SET POST CORNER TO SECTIONS 23-24-25 & 26, HEMLOCK 14 N 48 E 3, HEMLOCK 14 S 28 W 34

JULY 19, 1976, LCRC P.24 JUNIATA TWP., DAVID ROWE, PS 11192, FOUND COMPLETE CROCK, BROKEN, NO STONE. SET AXLE SHAFT, EAST 29.6' CENTER OLD CEDAR POST, S45°W 44.85' RLS 11192 TAG IN CORNER POST, S75°W 97.65' RLS11192 TAG IN 18" WHITE PINE

JAN. 18, 1978, SURVEY L.487 PP. 202-204, KENNETH DUNTON, PS 23503, FOUND AXLE SHAFT & CROCKERY, EAST 29.6' CENTER OLD CEDAR POST, S45°W 44.85' RLS 11192 TAG IN CORNER POST, S75°W 97.65' RLS11192 TAG IN 18" WHITE PINE, S60°W 62.90' NAIL IN 30" DOUBLE MAPLE

MAY 28, 1985, SURVEY L.550 P.775, LIONEL EMERY, PS 24593, AXLE SHAFT AND CROCKERY NOT FOUND, SET 1/2" RE-ROD FROM ACCESSORIES, S45°W 44.85' RLS 11192 TAG IN CORNER POST, S75°W 97.65' RLS11192 TAG IN 18" WHITE PINE, S60°W 62.90' RLS 11192 TAG IN 30" DOUBLE MAPLE

FEB. 11, 1991, SURVEY L.612 P.879, PAUL BROWN, PS 33134, FOUND 5/8" ROD, S60°W 62.86' NAIL HEAD IN 38" DOUBLE MAPLE, S45°W 44.80' SPIKE & TAG 11192 IN NE FACE A. POST/ NAIL NOT FLUSH, S45°E 33.16' SET SPIKE IN NE FACE 12" POPLAR, S15°E 42.52' SET SPIKE IN SW FACE 10" MAPLE, N40°W 60.4' SCAR ON E. FACE 12" WHITE PINE, S75°W 97.6± SCAR ON E. FACE 24" WHITE PINE

FEB. 25, 1991, LCRC P.53 JUNIATA TWP., PAUL BROWN, PS 33134, FOUND 5/8" ROD, S60°W 62.86' NAIL HEAD IN 38" DOUBLE MAPLE, S45°W 44.80' SPIKE & TAG 11192 IN NE FACE A. POST/ NAIL NOT FLUSH, S45°E 33.16' SET SPIKE IN NE FACE 12" POPLAR, S15°E 42.52' SET SPIKE IN SW FACE 10" MAPLE

JAN. 20, 1992, SURVEY L.631 PP.931-933, KENNETH DUNTON, PS 23503, FOUND 5/8" IRON ROD IN PLACE, S60°W 62.86' NAIL IN 38" DOUBLE MAPLE, S45°W 44.80' SPIKE & TAG 11192 IN NE FACE R.R. TIE COR. POST, S45°E 33.16' SPIKE IN NE FACE 12" POPLAR, S15°E 42.52' SPIKE IN SW FACE 10" MAPLE

MAY 7, 1993, SURVEY L.644 P.316, JONATHAN FIELD, PS 37276, SAME OBJECT AND ACCESSORIES AS SURVEY L.631, PP. 931-933

REMONUMENTATION

FEB 08 2001

SECTION

K-9 T12N-R8E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 5/8" BAR IN MIDDLE OF LARGE PIECES OF BROWN CROCKERY. RECOVERED 3 ACCESSORIES WHICH INDICATE THAT 5/8" BAR IS IN SAME POSITION AS SURVEYS AND LCRC'S CITED ABOVE.

ACCEPTED 5/8" BAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED 5/8" BAR AND SET 36" CONCRETE MONUMENT WITH STANDARD BRASS CAP STAMPED K-9, T12N-R8E.

N20°E, 28.02' FACE OF STEEL ROAD SIGN POST EAST, 8.0' SET CARSONITE POST

S50°E, 33.13' SET REMON. TAG & NAIL ABOVE FOUND SPIKE IN NE FACE OF 12" POPLAR

S45°W, 44.93' SET REMON. TAG & NAIL ABOVE FOUND NAIL & TAG IN NE FACE OF CORNER POST

S75°W, 98.32' SET REMON. TAG & NAIL IN NE FACE OF 24" WHITE PINE

N60°W, 62.84' SET REMON. TAG & NAIL ABOVE FOUND NAIL HEAD IN NE FACE OF 36" MAPLE

Signed by

Kari M. Loehla

Date 12/16/00

APPROVED BY TUSCOLA COUNTY REMONUMENTATION PEER GROUP

12/14/2000

ASD MWP RAB

Surveyor's Michigan License No. 44289



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971; REVISED MAY 14, 1975; REVISED JAN., 1983; REVISED OCT., 1991

