

FEB 08 2001

SECTION

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #95 Juniata

00 DEC 19 PM 1:33

Gregory M. Jensen
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File
Number

For corners in: JUNIATA TWP.

- Tuscola Located In: Corner Code #
(county)
- Public Land Survey T 12N R 8E K-10
T _____ R _____
T _____ R _____
T _____ R _____
 - Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
 - Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
 - Lot No. _____, Recorded Plat
 - Private Claims

I, Kari M. Lohela, in a field survey on November 11, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822 G.L.O. NOTES, ORANGE RISDON, D.S., SET ¼ SEC. POST, HEMLOCK 12 S 74 E 32, HEMLOCK 12 S 70 W 12
- JAN. 20, 1992, SURVEY L.631 PP.931-933, KENNETH DUNTON, PS 23503, SET 1½" X 4'-4" PIPE BY SINGLE PROPORTION METHOD, EAST 1.5' CENTERLINE N-S TRAIL, EAST 11.80' NAIL IN N. FACE 12" TREE, N65°E NAIL IN S. FACE OF WESTERLY TREE TWIN 24" TREE, S70°W 37.30' IN S. FACE 8" ASH, S70°E 33.80' NAIL IN S. FACE 15" TREE
- MAY 7, 1993, SURVEY L.644 PP.316-317, JONATHAN FIELD, PS 37276, SAME OBJECT AND ACCESSORIES AS SURVEY L.631 PP.931-932
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1½" PIPE AND REMAINS OF OLD BARBED WIRE FENCE. RECOVERED 2 ACCESSORIES WHICH INDICATE THAT 1½" PIPE IS IN SAME POSITION AS SURVEYS CITED ABOVE.
- ACCEPTED 1½" PIPE AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- REMOVED 1½" PIPE AND SET 36" CONCRETE MONUMENT WITH STANDARD BRASS CAP STAMPED K-10, T12N-R8E.
- EAST, 1.5'± CENTERLINE N-S TRAIL
S35°E, 28.03' SET REMON. TAG & NAIL IN NE FACE OF 4" BIRCH CLUSTER
S15°W, 23.00' SET REMON. TAG & NAIL IN E. FACE OF 4" MAPLE
S70°W, 37.34' SET REMON. TAG & NAIL ABOVE FOUND SPIKE IN S. FACE OF 8" ASH
WEST, 4.0' SET CARSONITE POST
N30°W, 19.98' SET REMON. TAG & NAIL IN E. FACE OF 10" TREE

SURVEY & REMONUMENTATION

FEB 08 2001

K-10 T12N-R8E

SECTION

signed by

Kari M. Ulla

Date 12/18/00

APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP

12/14/2000

*1300
MWP
RFB*

surveyor's Michigan License No.



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

