

SURVEY & REMONUMENTATION

COPY

FEB 08 2001

SECTION

2000 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: JUNIATA TWP.

- Tuscola Located In: Corner Code #
1. Public Land Survey T 12N R 8E K-12
2. Property Controlling S T R
3. Miscellaneous S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED FOR RECORD LIBER NO. PAGE NO. FILE NO. #92 Juniata

00 DEC 19 PM 1:33

Register of Deeds Stamp & File Number

I, Kari M. Lohela, in a field survey on November 11, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

\*1961, MSHD PROJECT 79041C, M-46 PLANS, SHEET 14, 1" IRON ROD, N 35 W 37.30' 8" ELM, S 70 E 28.81' 10" CEDAR, N 75 E 20.64' 7" ELM

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O. NOTES, ORANGE RISDON, D.S., SET 1/4 SEC. POST, W. MAPLE 12 N 33 E 22, LYNN 12 S 57 W 9

AUG. 26, 1895, EDWARD TESKEY, COUNTY SURVEYOR, EQUAL DISTANCE AND STUMP OF B.T., CEDAR 14 S 6 1/2 W 55 1/2, CEDAR STAKE 3 WEST 25

\* MAY 26, 1976, LCRC P.23 JUNIATA TWP., DAVID ROWE, PS 11192, FOUND 1" BAR, S70°E 28.97' RLS 11192 TAG 12" CEDAR, N20°E 35.06' RLS 11192 TAG 10" MAPLE, N50°E 33.29' RLS 11192 TAG 10" ASH

JULY 27, 1976, SURVEY L.485 PP.419-420, KENNETH DUNTON, PS 23503, NO MENTION OF OBJECT OR ACCESSORIES

JULY 27, 1976, SURVEY L.479 PP. 805-806, DAVID ROWE, PS 11192, NO MENTION OF OBJECT OR ACCESSORIES

MAY 31, 1977, SURVEY L.475 PP.415-417, KENNETH DUNTON, PS 23503, SAME OBJECT AND ACCESSORIES AS LCRC P.23 JUNIATA TWP.

AUG. 16, 1983, SURVEY L.540 PP.34-35, RICHARD BOLDT, PS 28405, SAME OBJECT AND ACCESSORIES AS LCRC P.23 JUNIATA TWP.

JAN. 8, 1993, SURVEY L.640 PP.1015-1016, JONATHAN FIELD, PS 37276, FOUND 1" BAR, S70°E 28.97' RLS 11192 TAG 18" CEDAR, N20°E 35.06' RLS 11192 TAG 14" MAPLE, N50°E 33.29' RLS 11192 TAG 16" ASH, WEST 97.11' FOUND 1/2" ROD

SEPT. 2, 1997, SURVEY L.736 P.944, JONATHAN FIELD, PS 37276, SAME OBJECT AND ACCESSORIES AS SURVEY L.640, PP.1015-1016

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1" BAR. RECOVERED 3 ACCESSORIES WHICH INDICATE THAT 1" BAR IS IN SAME POSITION AS SURVEYS AND LCRC CITED ABOVE.

ACCEPTED 1" BAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

Grid table with columns A-L and rows 1-13. Cell J12 contains a black dot.

