

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM

For corners in JUNIATA TWP.

TUSCOLA
(County)

Located In:

Corner Code #

1. Public Land Survey	T	12N	R	08E	K-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. # 77
Juniata Twp.
95 OCT 30 AM 9:35
VIRGINIA H. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 30 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1821 GLO; WAMPLER, D.S.; SET POST; BEECH 10 N27E 27LKS., HEMLOCK 40 S27W 27LKS.
- 1895 TESKEY, C.S.; SURVEY OF SEC.35; STONE SET BY J.A. TESKEY; NO WITS GIVEN
- 1895 TESKEY, C.S.; SURVEY OF SEC.36; "SEE S.E. CORNER OF SECTION 35 PAGE 277"; NO WITS GIVEN
- 1983 ROWE ENG.; BOLDT, P.S.#28405; SURVEY L.540 PG.34-5; FND BOAT SPIKE IN MON BOX; S75W 75.57' TAG IN 4" ASH, N50W 61.00' ROAD SIGN POST, N45E 69.07' TAG IN P.P., S60E 61.10' TAG IN 10" PINE
- 1983 BOLDT, P.S.#28405; LCRC PG.46; FND BOAT SPIKE IN MON BOX; SAME WITS AS 1983 SURVEY ABOVE
- 1992 ROWE ENG.; FIELD, P.S.#37276; SURVEY L.640 PG.1015-6; FND BOAT SPIKE IN MON BOX; SAME WITS AS 1983 SURVEY ALSO WEST 21.50' FND BOAT SPIKE IN MON BOX

DEC 01 1995

COMMISSIONER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995 ROWE ENG.; FIELD, P.S.#37276; FND BOAT SPIKE IN MON BOX AT C/L EXTENDED OF ASPH. ROAD TO N. AND 7'S. OF C/L GRAVEL ROAD TO W. AND 15'S. OF C/L GRAVEL ROAD TO E.; RECOVERED 2 PREV. WITS INDICATING THAT FND BOAT SPIKE IS IN SAME POSITION AS 1983 SURVEY ABOVE

ACCEPTED FND BOAT SPIKE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13 REPLACED BOAT SPIKE W/ 5/8" ROD W/ STANDARD REMON CAP IN CONC. IN MON. BOX
- N50°W, 61.00' CENTER OF ROAD SIGN POST STAMPED CAP "K 13 T12N R8E"
- S60°E, 61.10' FND. NAIL W/TAG #11192 IN N. FACE 18" PINE.
- S50°E, 52.42' P-K NAIL W/TAG #37276 IN SW FACE P.POLE
- N30°E, 77.46' P-K NAIL W/TAG #37276 IN SE FACE P.POLE
- WEST, 21.51' FND. BOAT SPIKE IN MON. BOX




Signed by Jonathan M. Field
Surveyor's Michigan License No. 37276

Date 10-27-95

APPROVED
10-16-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

COPY



SE 1/4
SEC 35
T12N-R8E

SW 1/4
SEC 36
T12N-R8E

