

**SURVEY &
REMONUMENTATION**

FEB 08 2001

COPY

SECTION

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74,
Mich. P.A. 1970**

For corners in: JUNIATA TWP.

Tuscola Located In: Corner code #
(County)

1. Public Land Survey T 12N R 8E L-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat

5. Private Claims

I, Kari M. Lohela, in a field survey on November 11, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #100 Juniata

00 DEC 19 PM 1:34

Arayn [Signature]
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5		4		3		2		1
3												
4	7			8		9		10		11		1
5												
6	18			17		16		15		14		1
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		2
11												
12	31			32		33		34		35		3
13												

A. Description of original monument and accessories and/or subsequent restoration:

1822 G.L.O. NOTES, ORANGE RISDON, D.S., SET ¼ POST, HEMLOCK 20 N 68 E 19, BEECH 6 S 48 W 19

NOV. 11, 1975, LCRC P.14 JUNIATA TWP., DAVID ROWE, PS 11192, FOUND NOTHING. SET T IRON AS OCCUPIED AT INTERSECTION OF VICKORY AND BALL ROADS. N45°W 45.72' NAIL & FLAGGING IN P.P., N45°E 39.02' NAIL & FLAGGING IN T.P., N65°E 49.13' CENTER OF ROAD SIGN

DEC. 5, 1975, SURVEY L.457 PP.770-772, JAMES BECK, PS 21559, FOUND 5/8" RE-ROD IN PLACE, N45°W 45.72' NAIL & FLAGGING IN P.P., N45°E 39.02' NAIL & FLAGGING IN T.P., N65°E 49.13' CENTER OF ROAD SIGN, SOUTH 23.76' PK & FLAGGING IN FENCE POST

JUNE 6, 1976, SURVEY L.461 PP.185-186, DAVID ROWE, PS 11192, FOUND 5/8" RE-ROD, N45°W 45.72' NAIL & FLAGGING IN P.P., N45°E 39.02' NAIL & FLAGGING IN T.P

JUNE 28, 1976, SURVEY L.462 PP.928-930, DAVID T. ROWE, PS 11192, FOUND 5/8" RE-ROD & CROCKERY, S65°E 3.85' TO 5/8" RE-ROD, N40°W 42.25' NAIL & FLAGGING IN P.P., N45°E 40.43' NAIL & FLAGGING IN T.P., N55°E 45.78' CENTER OF ROAD SIGN POST, S05°E 25.32' PK NAIL & FLAGGING IN FENCE POST, S05°E 34.72' FOUND ¾" PIPE

JULY 19, 1976, LCRC P.24 JUNIATA TWP., DAVID ROWE, PS 11192, FOUND OLD CORRODED 5/8" RE-ROD W/ABUNDANT OLD POTTERY, CROCKERY, S65°E 3.85' TO 5/8" RE-ROD, N40°W 42.25' NAIL & FLAGGING IN P.P., N45°E 40.43' NAIL & FLAGGING IN T.P., N55°E 45.78' CENTER OF ROAD SIGN POST, S05°E 25.32' PK NAIL & FLAGGING IN FENCE POST

NOV. 1, 1976, SURVEY L.467 P.801, DAVID ROWE, PS 11192, NO MENTION OF OBJECT OR ACCESSORIES

MAY 14, 1979, SURVEY L.498 P.1162, JAMES QUIST, PS 25868, FOUND 5/8" RE-ROD & CROCKERY, N40°W 42.25' NAIL & FLAGGING IN P.P., N45°E 40.43' NAIL & FLAGGING IN T.P

JAN. 18, 1978, SURVEY L.487 PP.202-204, KENNETH DUNTON, PS 23503, NO MENTION OF OBJECT OR ACCESSORIES

SECTIONS A., B., AND C. CONT. ON BACK OF FORM

SURVEY &
REMONUMENTATION

FEB 08 2001

SECTION

L-7 T12N-R8E

JULY 15, 1982, SURVEY L.536 PP.1309-1310, DAVID ROWE, PS 11192, FOUND 5/8" RE-ROD & CROCKERY, N40°W 42.25' NAIL & FLAGGING IN P.P., N45°E 40.43' NAIL & FLAGGING IN T.P., S65°E 3.85' TO 5/8" RE-ROD

AUG. 7, 1987, SURVEY L.578 P.38, KENNETH DUNTON, PS 23503, FOUND SAME OBJECT AND ACCESSORIES AS SURVEY L.536, PP.1309-1310

DEC. 15, 1987, SURVEY L.578 PP.1255-1257, KENNETH DUNTON, PS 23503, NO MENTION OF OBJECT OR ACCESSORIES

JUNE 22, 1988, SURVEY L.583 P.1230, KENNETH DUNTON, PS 23503, FOUND SAME OBJECT AND ACCESSORIES AS SURVEY L.536, PP.1309-1310

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 5/8" BAR AND NUMEROUS PIECES OF BLUE CROCKERY. RECOVERED 4 ACCESSORIES WHICH INDICATE THAT 5/8" BAR IS IN SAME POSITION AS SURVEYS STARTING IN 1976, AND 1976 LCRC CITED ABOVE.
ACCEPTED 5/8" BAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RAISED 5/8" BAR WITH 5/8" BAR AND SET STANDARD BRASS CAP STAMPED L-7, T12N-R8E. ENCASED CAP AND BAR IN CONCRETE IN NEW MONUMENT BOX.
N45°E, 53.10' SET REMON. TAG & NAIL ABOVE FOUND PK NAIL & TAG IN W. FACE OF CUTOFF UTILITY POLE
N65°E, 45.60' CENTER OF STEEL ROAD SIGN POST
S65°E, 3.85' FOUND 5/8" REBAR
SOUTH, 44.82' SET REMON. TAG & NAIL ABOVE FOUND NAIL & WASHER IN W. FACE OF 18" PINE
S40°W, 53.72' SET REMON. TAG & NAIL IN N. FACE OF 6" PINE
N35°W, 42.06' SET REMON. TAG & NAIL ABOVE FOUND PK NAIL IN E. FACE OF UTILITY POLE

Signed by

Kari M. Lohela

Date 12/14/00

APPROVED BY TUSCOLA COUNTY
REMONUMENTATION PEER GROUP

MWP
KRB

Surveyor's Michigan License No. ~~44289~~

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197

REVISED MAY 14, 197

REVISED JAN., 198
REVISED OCT., 199



SURVEY &
REMONUMENTATION

FEB 08 2001

L-7 T12N-R8E

