

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM

For corners in JUNIATA TWP.
TUSCOLA
(County)

Located In:

Corner Code #

1. Public Land Survey	T	12N	R	08E	L-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 30 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 GLO; WAMPLER, D.S.; SET POST; HEMLOCK 7 EAST 2LKS., CEDAR 15 S86W 21LKS.
1895 TESKEY, C.S.; STAKE PREVIOUSLY ESTABLISHED; NO WITS GIVEN
1979 ROWE ENG.; WOLOSZEN, WIT CARD ON FILE AT REI; FND NOTHING, SET 1/2" ROD BASED ON IRONS FND AND SURVEY BY CO. SURVEYOR DATED 1895; S30W 28.17' TAG #11192 IN FENCE POST, N30E 22.14' TAG #11192 IN T.P., N40W 39.14' TAG #11192 IN FENCE POST, WEST 10' FENCE LINE S., SOUTH 2' C/L GRAVEL E-W

SURVEY &
MICHIGAN COMMISSION
DEC 4 1995
COMMISSION


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD 2' N. OF C/L GRAVEL ROAD E-W AND ON TREE LINE TO N.; RECOVERED 2 PREV. WITS INDICATING THAT FND 1/2" ROD IS IN SAME POSITION AS 1979 ROD CITED ABOVE

ACCEPTED FND ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 REPLACED FND. 1/2" ROD W/ STANDARD REMON MONUMENT STAMPED CAP "L13 T12N R8E"
N40°W, 39.46' FND. NAIL W/TAG #11192 IN SW FACE FE COR. POST (LEANING NW'LY)
WEST, 10'± FENCE LINE TO S.
N20°E, 26.77' NAIL W/TAG #37276 IN SE FACE 10" ELM IN CLUMP
N70°W, 54.29' NAIL W/TAG #37276 IN S. FACE 10" POPLAR
S45°E, 66.74' P-K NAIL W/TAG #37276 IN SW FACE P.POLE



Signed by Jonathan M Field Date 10-27-95
Surveyor's Michigan License No. 37276

APPROVED
10-16-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

COPY

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #78
95 OCT 30 AM 9:35
Juniata Twp.
VIRGINIA M. McLAUREN
TUSCOLA COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

