

**SURVEY &  
REMONUMENTATION**

DEC 02 1993

**COMMISSION**

**1993 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
JUNIATA TOWNSHIP**

For corners in

TUSCOLA

(County)

Located In:

Corner Code #/

- |                                    |                          |       |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey              | T <u>12N</u> R <u>8E</u> | M-3   |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. # 65  
JUN 11 1993  
93 OCT 22 PM 2:44  
VIRGINIA R. HESLER  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth D. Dunton, in a field survey on July 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes Joseph Wampler, D.S. Set post cor. Sec. 1 & 12 Beech 9" N38°W 7.26' Sugar 14" S43°E 11.88'	Dec., 1988 brass top monument found by me and used to establish cor. M-4. Corner M-3 not shown on surveys. No accessories given.
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found & accepted 4" brass plate marked State of Michigan atop 4" steel casing 6" below gravel grade. Corner identified by markings on monument as NE corner Sec. 12, T12N-R8E. Measured distance of 2607.80' between corner M-3 and corner M-4.

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

State of Michigan monument found is substantial. Did not replace with standard Tuscola County monument.  
S01°57'10"W 103.37' found 4" brass plate - State of Michigan mon. (1/2 plate missing).  
S01°51'30"W 41.7' physical centerline asphalt pave. NW & SE.  
N85°24'20"W 100.00' set 1/2" rod along section line.  
N17°04'W 97.04' set spike in E. face Southerly tree of twin 24" elm.  
S80°05'E 34.06' set T.C. Re-mon. tag & spike over #11192 tag in S. face of p. pole.

Signed by [Signature] Date Oct. 11, 1993  
Surveyor's Michigan License No. 23503



APPROVED  
10-11-93

