

**SURVEY & REMONUMENTATION**

**MAR 05 1998**

1997 REMONUMENTATION PROGRAM

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. 84

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

FILE NO. INDIANFIELDS TOWNSHIP  
97 NOV -5 PM 4:01

For corners in Indianfields Twp.

Tuscola _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12N</u> R <u>09E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*George W. Dunton*  
TUSCOLA COUNTY  
REGISTER OF DEEDS

**COPY**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kenneth D. Dunton, in a field survey on Sept. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
March 20, 1834 Hervey Parke, D. S. Set post for Sections 32 & 33. Hemlock 18" N46°W 30 1/2 links, Birch 7" N67°E 18 links. Jan. 18-27, 1898 G. B. Felton, Co. Surveyor, Survey of Section 32, T12N-R9E. SE corner set from measure, c.p. & crockery at corner. March 20-24, 1900 G. B. Felton, Co. Surveyor, Survey of Section 33, T12N-R9E. SW corner prev. set from measure. Cedar post and crockery at corner. Oct. 1960 M.S.H.D. witness card, E. C. Parker, Survey Chief, found 1" axle shaft 3' down. Set 3/4" pipe above. N43°W 52.74' 1" gas pipe, N12°W 51.69' cor. fen. post, South 52.30' tacked hub stake. May 8, 1972 L.C.R.C. Page 6 by Elrich, L.S. #18986. Fnd. mon. box in conc. pavt., N15°W 65.0' centerline of top of conc. culvert, N25°E 69.5' centerline of top of conc. culvert.  
(Section A cont. on back of form)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron bar in monument box and two accessories that indicate the corner found is in the same position as the 1973 survey. Accepted 1" iron as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Placed standard brass cap over 1" iron bar found in monument box. Stamped cap E-13, T12N-R9E. Encased cap in concrete in monument box.  
N18°W 65.05' to West end of 48' of 24" concrete culvert.  
N25°E 69.42' to East end of 48' of 24" concrete culvert.  
East 121.06' fnd. boat spike in monument box @ apparent cor. E-1, T11N-R9E.  
South 2.64' centerline joint of E-W concrete pavement.

Signed by *Kenneth D. Dunton*  
Surveyor's Michigan License No. 23503

Date 10-20-97

**APPROVED**  
10-20-97  
*[Signature]*



