

SECTION

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 88

1997 REMONUMENTATION PROGRAM FILE NO. _____
LAND CORNER RECORDATION CERTIFICATE INDIANFIELDS TOWNSHIP
Filing Requirement of Act 74, Mich. P.A. 1970 97 NOV -5 PM 4:02

For corners in Indianfields Twp.

<u>Tuscola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T12N R09E</u>	<u>I-13</u>
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

Christina M. Brown
TUSCOLA COUNTY
REGISTER OF DEEDS

COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on Sept. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

March 19, 1834 Hervey Parke, D.S. Set post corner Sections 34 & 35. Beech 8" N62 1/2° 19 links, Beech 12" N77°W 33 links. Jan. 1961 M.S.H.D. witness card, E. C. Parker, Survey Chief. Found boat spike in mon. box. N65°E 82.57' p. pole, N32°W 61.93' SE cor. gas pump island, S32°W 33.92' p. pole. Sept. 5, 1968 M.S.H.D. witness card, R. Fosdick, Survey Chief, boat spike in mon. box. N70°W 74.00' to curb end joint, N60°E 85.80' to p. pole, S45°W 50.60' to p. pole. Feb. 7, 1977 survey L-475, P-418, 419 & 420 by Dunton, L.S. #23503 with Rowe Eng. Boat spike in mon. box. N70°W 74.00' curb end joint, N60°E 85.80' p. p., S45°W 50.60' p.p. Nov. 3, 1980 survey L-511, P-878 & 879 by Fokens, L.S. #21567. Fnd. mon. box.
(Sec. A con't on back of form)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in monument box and one accessory that indicates the corner found is in the same position as the 1968 M.S.H.D. witness card. Accepted 1" pipe as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap over 1" pipe found in monument box. Stamped cap I-13, T12N-R9E. Encased cap in concrete in monument box.
N57°E 92.25' set T. C. Remon. tag & spike in NW face light pole.
N70°W 74.01' set 1/2" x 18" iron rod & cap #23503 @ back of conc. curb.
S26°W 53.79' fnd. nail & tag #17623 in NW face light pole.
East 71.40' top center mon. box @ centerline P.C.
East 56.94' fnd. 1" pipe in mon. box at apparent cor. I-1, T12N-R9E.

Signed by *Kenneth D. Dunton*
Surveyor's Michigan License No. 23503

Date 10-9-97



APPROVED
10-27-97
[Signatures]

Section A con't. from front of form:

Accessories same as L-475, P-418, 419 & 420. March 17, 1983 L.C.R.C. Page 48 by Emery, L.S. #24593. Found 1" pipe in mon. box N60°E 85.65' nail in p. pole, East 71.5' center lug mon. box cover, S65°E 141.47' M.S.H.D. tag in p. pole, S25°W 50.71' M.S.H.D. tag in p. pole. March 21, 1983 survey L-531, P-108 by Emery, L.S. #24593. Same object and accessories as L.C.R.C. Page 48. Oct. 5, 1984 surveys L-547, P-1446 through 1457 by Fluharty, L.S. #18223. Fnd. mon. box. Accessories same as L-511, P-878 & 879.

