

SURVEY & REMONUMENTATION

MAR 05 1998

1997 REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kingston Township

<u>Tuscola</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T12N R11E	C-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #62
97 NOV 12 PM 3:47
TUSCOLA COUNTY REGISTERED OFFICES
COPY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on Sept. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

March 18, 1834 Hervey Parke, D.S. Set post corner Sections 31 & 32. Beech 12" N30°E 27 links, Sugar 24" N57°W 28 links. July 1963 M.S.H.D. witness card, H. G. McManus, Survey Chief, 1" iron. N45°E 75.20' p. pole, N25°W 74.99' t. pole, S30°W 65.15' t. pole. Sept. & Oct. 1971 two L.C.R.C. forms, pages 1 & 5 filed by Rowe, L.S. #11192. Found 1 1/4" pipe. North 19.87' centerline M-46, West 4'± centerline Phillips Road ext., East 27.02' w'ly. guard rail post. Oct. 14, 1971 survey L-1, P-239 & 240 by Rowe, L.S. #11192. Same object as L.C.R.C. forms, Pages 1 & 5. Feb. 4, 1972 survey L-1, P-366 & 367 by Rowe, L.S. #11192. Same object and accessories as survey L-1, P-239 & 240. June 12, 1981 survey L-516, P-827 by Emery, L.S. Section A con't on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in place and one accessory that indicates the corner found is in the same position as the 1971 L.C.R.C. forms. Accepted 1" pipe as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1" pipe and placed concrete monument with standard brass cap stamped cap C-13, T12N-R11E. Placed monument box over monument. North 19.87' E-W centerline conc. pavement M-46. S80°E 27.62' set T. C. Remon. tag & spike atop new guard rail post. S86°W 6.11' fnd. 1" pipe. N88°W 264.52' fnd. 1" pipe at apparent cor. C-1, T11N-R11E. N89°W 270.07' fnd. 1/2" iron rod.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date 11-10-97

KENNETH D. DUNTON
LAND SURVEYOR
No. 23503

STATE OF MICHIGAN
LICENSED PROFESSIONAL SURVEYOR

APPROVED
11-10-97
[Signatures]

Section A con't from front of form:

Same object and accessories as survey L-1, P-366 & 367. Aug. 22, 1985 survey L-553, P-365 by Emery, L.S. #24593. Same object and accessories as survey L-516, P-827. March 28, 1990 survey L-615, P-692 by Gravlin, L.S. #23510. Same object and accessories as survey L-553, P-365. July 6, 1994 survey L-667, P-983 & 984 by Field, L.S. #37276. Found 1" pipe. N89°W 270.03' fnd. 1/2" rod, S86°W 6.10' fnd. 1" pipe, N88°W 264.50' fnd. 1" pipe, North 19.91' centerline joint in conc. pave.

