

**SURVEY & REMONUMENTATION**

MAY 05 1997

**COMMISSION**

**1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KINGSTON TOWNSHIP

TUSCOLA \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code // \_\_\_\_\_  
(County)

1. Public Land Survey T12N R11E **M-13** ✓  
T R  
T11N R11E **M-1**  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
LIBER NO. \_\_\_\_\_ PAGE NO. 59  
FILING NO. Kingston  
DEC 12 1996  
TIME: 3:30 P.M.  
GINNY McLAREN, REGISTER OF DEEDS  
TUSCOLA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Lionel Roy Emery, in a field survey on July 4, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S. -Set temporary Township corner at 80.00 chains Township corner established at 79.21 chains- Hemlock 15 North 7; Hemlock 28 S29W 8½; W. Ash 20 N6E 29; Hemlock 28 S29W 8½; Birch 17 S29W 41; Hemlock 28 S29W 21½
- 1882 (County Surveyor's Record) John A. Teskey, Tuscola County Surveyor -Established proportionate distance from identified corners and sight trees- Stake S45W 70 links; Stake N45W 70 links
- 1963 (Michigan State Highway Department witness card) Donald C. Pyle, P.S. 3165 - Found 1" Pipe buried 2' deep - S22°E 62.42' 29" Elm; N20°E 90.15' 26" Tw Elm; North 90.39' 27" Tw Elm
- 1987 (Survey -Liber 578, pages 58 and 59) Kenneth D. Dunton, P.S. 23503 -Fnd 1" pipe in Mon. box- North 1.0' center line of M-46; S20°W 56.3' S end of curb; S45°W 48.9' W end of curb

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" inside diameter Pipe in Monument Box together with Dunton's accessories

Accepted Pipe as marking original Township corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 5/8" diameter by 12" long reinforcing rod with Tuscola County Standard 2" Brass cap affixed inside found 1" Pipe. Stamped Cap M1 T11N/R11E and placed concrete inside Monument Box (Monument placed August 20, 1994)

- N50°E, 46.29' set ½" diameter reinforcing rod
- S40°E, 48.28' set ½" diameter reinforcing rod 1 ft. behind back of curb
- S50°W, 45.70' set ½" diameter reinforcing rod 1 ft. behind back of curb
- N40°W, 44.63' set ½" diameter reinforcing rod

NOTE: This corner is common with: M-1, T11N-R11E

Signed by Lionel Roy Emery  
Surveyor's Michigan License No. 24593

Date November 27, 1996

APPROVED  
12-71-96  
*[Signature]*



