

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 70
FILE NO. Gilford

Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 8:58

Gregory M. Field

TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in GILFORD TWP.
TUSCOLA Located In: Corner Code #
(County)

1. Public Land Survey	T <u>13N</u> R <u>07E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MAY 15 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; SUGAR 12 S3W 35LKS, LYNN 16 N15E 31LKS
1974 ROWE, P.S. 11192; LCRC P19; FND 3/4" PIPE RAISED W/ 1/2" ROD W/CAP NORTH 60.35' RLS 11192 TAG IN 6" ELM, NORTH 65.08' RLS 11192 TAG IN FP, NORTH 23'± C/L DRAIN
1996 ROWE ENG.; FIELD, P.S.#37276; SURVEY L.695, PG.481; FND 1/2" ROD; SOUTH 3.0' CENTERLINE PAV'T; NORTH 32.23' S. EDGE STEEL FENCE POST; N45W 37.80' CENTER S. END CMP; S45W 18.36' SET P-K NAIL; S45E 19.02' SET P-K NAIL

NOTE: THIS CORNER IS NOT COMMON WITH B-1 T12N-R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD INSIDE 3/4" PIPE SURROUNDED BY STONES & SOME CROCKERY 3.0' N. OF C/L VAN GIESEN ROAD E-W; IN LINE WITH TREE ROW TO N.

ACCEPTED FND. 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-13 REPLACED 1/2" ROD W/ STANDARD REMONUMENT STAMPED "B 13 T13N R7E" IN MON. BOX
NORTH, 32.23' S. EDGE OF STEEL FENCE POST
N45°W, 37.80' FND. CHIS. NOTCH IN S. END CMP
S45°W, 18.36' FND. P-K NAIL
S45°E, 19.02' FND. P-K NAIL



Signed by Jonathan M. Field Date 11-6-96
Surveyor's Michigan License No. 37276

APPROVED
11-4-96
[Signature]

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

