

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 65
TOWNSHIP Calford

96 DEC 10 AM 8:57

Jonathan M. Field
TUSCOLA COUNTY
REG. SURVEYOR

Register of Deeds Stamp & File Number

For corners in GILFORD TWP.
TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 13N R 07E _____ G-13 _____
T _____ R _____ _____
T _____ R _____ _____
T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 15 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; BEECH 4 N58E 43LKS, W OAK 14 N51W 1.80 CH
1974 ROWE, P.S.#11192; LCRC PG.14; SET 1/2" IRON 29.70' W OF NW COR SEC 3 T12N-R7E PER GLO NOTES; S70E 38.10' NE COR. BRIDGE ABUT., S45E 14.94' NW COR. BRIDGE ABUT., EAST, 29.70' NW COR. SEC.3 T12N-R7E
1977 LEACH ENG.; TOMMER, P.S.#22444; SURVEY OF NW 1/4 SEC.3 T12N-R7E; G-13 USED AS WITNESS OF WEST 29.70' FROM G-1 T12N-R7E

GLO NOTES FOR T12N-R7E INDICATE THAT THIS CORNER IS NOT COMMON WITH G-1 T12N-R7E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD 16' S. OF C/L ASPH. RD. E-W & ON C/L EXTENDED OF APSPH. RD. TO N. RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND ROD IS IN SAME POSITION AS 1974 LCRC CITED ABOVE

ACCEPTED 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 REPLACED FND ROD W/ STANDARD REMON MONUMENT STAMPED "G 13 T13N R7E" IN MON. BOX
S12°E, 28.75' SET 1/2" ROD W/CAP #37276
N89°E, 29.70' FND. 3/8" ROD AT APPARENT G-1, T12N-R7E
N40°E, 83.50' SET P-K NAIL W/TAG #37276 IN SE FACE P.POLE
N34°W, 50.38' SET 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 11-6-96
Surveyor's Michigan License No. 37276

APPROVED 11-4-96

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR LAND PROCESSING MARCH, 1993

29

