

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED FOR RECORD
BOOK NO. _____ PAGE NO. 56
ACCORD TO Gilford

95 DEC 10 AM 8:56

For corners in GILFORD TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>07E</u>	<u>M-4</u> ✓
	T _____ R _____	_____
	T <u>13N</u> R <u>8E</u>	<u>A-4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jonathan M. Field
THASOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; W MAPLE 30 N42W 55 LKS, ELM 40 S24W 64LKS
1869 CRANSTON, C.S.; SURVEY IN W. 1/2 SEC.12 T13N-R7E; NO OBJECT STATED; NO WITS GIVEN
1983 BOLDT, MC LEOD & JOHNSON, INC.; DRAIN PLANS (EMJ JOB NO.482-3); INDICATE THAT CORNER FALLS IN OPEN DITCH (NORTHWEST DRAIN), NO OBJECT STATED, NO WITS GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. NO EVIDENCE OF CORNER MONUMENTATION (POSITION FALLS IN CENTER OF LARGE OPEN DITCH "NORTHWEST DRAIN")

ESTABLISHED POSITION OF CORNER BY SINGLE PROPORTION BETWEEN M-3 & M-5 T13N-R7E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-4 WITNESS MONUMENT SET 185' NORTH & ON LINE BETWEEN M-5 & M-3 T13N-R7E

SET STANDARD REMON MONUMENT STAMPED "M 4 W.C. T13N R7E" ACCESSORIES ARE TO WIT. COR. MONUMENT NOT M-4
N48°W, 22.85' SET 1/2" ROD W/CAP #37276
N36°E, 30.41' SET 1/2" ROD W/CAP #37276
S87°E, 36.02' SET 1/2" ROD W/CAP #37276
S39°E, 57.63' SET NAIL W/TAG #37276 IN W. FACE 12" ELM

NOTE: CORNER M-4 T13N-R7E IS COMMON WITH A-4 T13N-R8E

Signed by Jonathan M. Field Date 11-29-96
Surveyor's Michigan License No. 37276



APPROVED
11-27-96
L.P.C.
RAB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

Doc

