

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 55
RECORDED Gilford
96 DEC 10 AM 8:56

For corners in GILFORD TWP.
TUSCOLA
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>T13N</u> R <u>R07E</u> | <u>M-5</u> |
| | T _____ R _____ | _____ |
| | T <u>T13N</u> R <u>R8E</u> | <u>A-5</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 17 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET POST; LYNN 12 N49W 19LKS, ELM 18 S65W 28LKS
1869 CRANSTON, C.S.; SURVEY IN W 1/2 OF SEC.12 T13N-R7E; NO OBJECT STATED; NO WITS GIVEN
1957 BLACK, P.S.; UNRECORDED SURVEY; NO OBJECT STATED; NO WITS GIVEN
1971 HENDERSON & BATES; BATES, P.S.#16699; SURVEY L.1, PG.296; NO OBJECT STATED; N45W 33.15' NAIL & CAP T/P, N5E 16.15' W LEG OF ARROW SIGN, S45E 75.0' NAIL & CAP P/P.
1975 ROWE ENG.; BECK, P.S.#21559; SURVEY L.458, PG.215-217; FND 3/4" PIPE; N50W 33.15' NAIL & WASH. T/P, N50E 16.18' W LEG ROAD SIGN, S50E 75.05' NAIL & WASHER IN P/P
1975 BECK, P.S.#21559; LCRC PG.24; SAME OBJECT AND WITS AS 1975 SURVEY ABOVE

GLO NOTES FOR T13N-R8E INDICATE THAT THIS CORNER IS COMMON WITH A-5 T13N-R8E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 3/4" PIPE IN MON. BOX ON C/L ASPH. ROAD TO S. & 1.5' N. OF C/L ASPH. ROAD E-W. RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND PIPE IS IN SAME POSITION AS 1971 SURVEY CITED ABOVE

ACCEPTED FND. PIPE IN MON BOX AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-5 SET 5/8" ROD W/STANDARD REMON CAP STAMPED "M 5 T13N R7E" INSIDE FND 3/4" PIPE, ENCASED BOTH IN CONC. IN MON BOX

- S55°E 35.90' CENTER OF RD SIGN POST
S60°E 75.00' FND. NAIL W/TAG IN NE FACE P. POLE
N05°E 16.27' W. EDGE OF W. SIGN POST LEG
N60°W 35.70' CENTER OF PHONE RISER
S45°W 35.95' SET 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 11-29-96
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
11-27-96
L.P.E.
K.S.B.

