

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
PAGE NO. 52
FILE NO. Gilford

For corners in GILFORD TWP.
TUSCOLA
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 13N R 07E M-8 ✓
T _____ R _____
T 13N R 8E A-8
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

96 DEC 10 AM 8:55

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1834 GLO; RISDON, D.S.; SET POST; BEECH 8 N51E 15LKS, BEECH 10 S47W 17LKS
 1971 KAY ENG.; KAY, P.S.#14096; SURVEY L.1, PG.312; FND 3/8" ROD; N85E 69.90' 18" PINE, S45E 40.70' 8" MAPLE, S87W 35.65' T/P
 1979 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.497, PG.970; SET RR SPIKE W/ "+"; N85E 69.80' 18" PINE, S45E 40.70' 8" MAPLE, WEST 32.80' IRON W/ CAP RLS 14096
 1979 QUIST, P.S.#25868; LCRC PG.30; RESET COR BASED ON KAY TIES; NO OBJECT STATED; SAME WITS AS 1979 SURVEY ABOVE

NOTE: THIS CORNER IS COMMON WITH A-8 T13N-R8E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996 ROWE ENG.; FIELD, P.S.#37276; FND. RR SPIKE 4.5' E. OF C/L ASPH. ROAD N-S & ON OCCUPIED TREE LINE TO W. RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND RR SPIKE IS IN SAME POSITION AS 1971 SURVEY CITED ABOVE

ACCEPTED FND. RR SPIKE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-8 REPLACED FND RR SPIKE W/ STANDARD REMON MONUMENT STAMPED "M 8 T13N R7E" IN MON. BOX
 S82°W, 36.03' SET NAIL W/REMON TAG IN S. FACE T. POLE
 N74°E, 70.88' SET NAIL W/REMON TAG IN NW FACE 20" SPRUCE
 S49°E, 41.25' SET NAIL W/REMON TAG IN NE FACE 24" MAPLE
 S50°W, 26.12' SET 1/2" ROD W/CAP #37276

Signed by Jonathan M. Field Date 11-6-96
 Surveyor's Michigan License No. 37276

APPROVED
11-4-96
*1500
 JAG
 JPL
 JCS*



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 2, 1971
 REVIS. MAY 14, 1975
 REVIS. JUN 1983
 REVIS. MAR 1993

FAIRGROVE ROAD



M-7

179°56'59"

A-7

SEC. 24
T13N-R7E

M-8

179°59'26"

A-8

VASSAR ROAD

SEC. 19
T13N-R8E

1996 REI 2635.00'
1834 GLO 2640'

1996 REI 2636.46'
1834 GLO 2640'

DECKERVILLE ROAD



M-9

180°00'36"

A-9