

**1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**

RECEIVED FOR RECORD  
LICENSER NO. \_\_\_\_\_ PAGE NO. 49  
FILE NO. Gilford

Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 8:56

*Jonathan M. Field*  
TUSCOLA COUNTY  
REGISTER OF DEEDS

For corners in GILFORD TWP.  
TUSCOLA (County) Located In: Corner Code #

1. Public Land Survey T 13N R 07E M-11 ✓  
T \_\_\_\_\_ R \_\_\_\_\_  
T 13N R 8E A-11  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLO; RISDON, D.S.; SET POST; SUGAR 14 S53W 41LKS, W MAPLE 14 N51W 41LKS  
1971 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.1, PG.321; FND 1" PIPE; N50W 84.10' BLDG COR STORE, N45E 52.54' NAIL & CAP IN P/P, WEST 2.5' C/L RD  
1971 ROWE, P.S.#11192; LCRC PG.1; FND 1" PIPE; N50W 84.10' SE COR STORE, N35W 54.48' S. COR CONC BASE SIGN POST, N45E 52.54' NAIL & CAP IN P/P  
1973 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.433, PG.114; NO OBJECT STATED; NO WITS GIVEN

GLO NOTES FOR T13N-R8E INDICATE THAT THIS CORNER IS COMMON WITH A-11 T13N-R8E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD INSIDE 3/4" PIPE IN MON. BOX 4.5' S. OF C/L ASPH. ROAD E-W & 3'E. OF C/L ASPH. ROAD N-S. RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND ROD IS IN SAME POSITION AS 1971 SURVEY CITED ABOVE.

ACCEPTED FND. ROD IN PIPE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-11 REPLACED FND ROD IN PIPE W/ 5/8" ROD W/STANDARD REMON CAP STAMPED "M 11 T13N R7E" ENCASED IN CONC. IN MON. BOX

S48°W, 30.96' SET 1/2" ROD W/CAP #37276  
S41°E, 46.70' FND. NAIL IN SW FACE P. POLE  
N46°E, 43.04' CHIS. NOTCH IN TOP N. END 18" CMP  
N52°W, 79.19' NE CORNER OF BRICK ENCLOSED PORCH  
N55°W, 84.22' SE CORNER OF BRICK ENCLOSED PORCH (1971 LCRC REFERANCE TO SE COR STORE)

Signed by Jonathan M. Field Date 11-6-96  
Surveyor's Michigan License No. 37276

APPROVED  
11-6-96



MAY 20 1997

COMMISSION

20

