

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 86
TOWN Fairgrove
96 DEC 10 AM 8:59

For corners in FAIRGROVE TWP.
TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 13N R 08E A-8
T _____ R _____
T13N R 7E M-8
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

- A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET AS M-8 OF THE ORIGINAL GOVERNMENT SURVEY OF T13N-R7E; POST; BEECH 8 N51E 15LKS, BEECH 10 S47W 17LKS
1971 KAY ENG.; KAY, P.S.#14096; SURVEY L.1, PG.312; FND 3/8" ROD; N85E 69.90' 18" PINE, S45E 40.70' 8" MAPLE, S87W 35.65' T/P
1979 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.457, PG.970; SET RR SPIKE W/ "+"; N85E 69.80' 18" PINE, S45E 40.70' 8" MAPLE, WEST 32.80' IRON W/ CAP RLS 14096
1979 QUIST, P.S.#25868; LCRC PG.30; RESET COR BASED ON KAY TIES; NO OBJECT STATED; SAME WITS AS 1979 SURVEY ABOVE

NOTE: THIS CORNER IS COMMON WITH M-8 T13N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. RR SPIKE 4.5' E. OF C/L ASPH. ROAD N-S & ON OCCUPIED TREE LINE TO W. RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND RR SPIKE IS IN SAME POSITION AS 1971 SURVEY CITED ABOVE

ACCEPTED FND. RR SPIKE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-8 REPLACED FND RR SPIKE W/ STANDARD REMON MONUMENT STAMPED "M 8 T13N R7E" IN MON. BOX
S82°W, 36.03' SET NAIL W/REMON TAG IN S. FACE T. POLE
N74°E, 70.88' SET NAIL W/REMON TAG IN NW FACE 20" SPRUCE
S49°E, 41.25' SET NAIL W/REMON TAG IN NE FACE 24" MAPLE
S50°W, 26.12' SET 1/2" ROD W/CAP #37276

Signed by Jonathan M. Field Date 11-6-96
Surveyor's Michigan License No. 37276



APPROVED
11-6-96
[Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

REMONUMENTATION
MAY 29 1997
COMMISSION

