

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 83
FILE NO. Fairgrove
96 DEC 10 AM 8:59

For corners in FAIRGROVE TWP.

TUSCOLA (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 13N R 08E A-11 ✓
T _____ R _____
T 13N R 7E M-11
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 GLO; RISDON, D.S.; SET AS M-11 OF THE ORIGINAL GOVERNMENT SURVEY OF T13N-R7E; POST; SUGAR 14 S53W 41LKS, W MAPLE 14 N51W 41LKS
 - 1971 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.1, PG.321; FND 1" PIPE; N50W 84.10' BLDG COR STORE, N45E 52.54' NAIL & CAP IN P/P, WEST 2.5' C/L RD
 - 1971 ROWE, P.S.#11192; LCRC PG.1; FND 1" PIPE; N50W 84.10' SE COR STORE, N35W 54.48' S. COR CONC BASE SIGN POST, N45E 52.54' NAIL & CAP IN P/P
 - 1973 ROWE ENG.; ROWE, P.S.#11192; SURVEY L.433, PG.114; NO OBJECT STATED; NO WITS GIVEN

GLO NOTES FOR T13N-R8E INDICATE THAT THIS CORNER IS COMMON WITH M-11 T13N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD INSIDE 3/4" PIPE IN MON. BOX 4.5' S. OF C/L ASPH. ROAD E-W & 3'E. OF C/L ASPH. ROAD N-S. RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND ROD IS IN SAME POSITION AS 1971 SURVEY CITED ABOVE.

ACCEPTED FND. ROD IN PIPE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-11 REPLACED FND ROD IN PIPE W/ 5/8" ROD W/STANDARD REMON CAP STAMPED "M 11 T13N R7E" ENCASED IN CONC. IN MON. BOX

- S48°W, 30.96' SET 1/2" ROD W/CAP #37276
- S41°E, 46.70' FND. NAIL IN SW FACE P. POLE
- N46°E, 43.04' CHIS. NOTCH IN TOP N. END 18" CMP
- N52°W, 79.19' NE CORNER OF BRICK ENCLOSED PORCH
- N55°W, 84.22' SE CORNER OF BRICK ENCLOSED PORCH (1971 LCRC REFERENCE TO SE COR STORE)

Signed by Jonathan M. Field Date 11-6-96

Surveyor's Michigan License No. 37276

APPROVED
11-4-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 1971
37276 REVISED MAY 1975
REVISED MAR 1983
REVISED APR 1983
REVISED APR 1983



MAY 2 9 1997
COMMISSION

20



GILFORD ROAD

SEC. 36
T13N-R7E

M-12

180°06'24"

1996 REI 2635.40'
1834 GLO 2640'

A-12

VASSAR ROAD

M-11

179°51'24"

1996 REI 2628.89'
1834 GLO 2640'

A-11

VASSAR ROAD

SEC. 25
T13N-R7E

M-10

180°00'24"

A-10

SEC. 31
T13N-R8E

SEC. 30
T13N-R8E