

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED ON RECORD
LICER NO. _____ PAGE NO. 82
REC'D BY Fairgrove
56 DEC 10 AM 8:59

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in FAIRGROVE TWP.
TUSCOLA Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 13N R 08E A-12
T _____ R _____
13N R 7E M-12
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on MAY 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; RISDON, D.S.; SET AS M-12 OF THE ORIGINAL GOVERNMENT SURVEY OF T13N-R7E; POST;
BEECH 14 N60W 47LKS, SUGAR 24 S65E 15LKS
1976 BECK, P.S.#21559; LCRC PG.23; FND 1/2" ROD; N20W 95.06' TAG 11192 IN T/P, N60E 37.48'
NAIL & WASHER IN P/P, EAST 1.5' C/L ROAD
1988 ROWE ENG; SZYSZKOSKI, P.S.#33986; SURVEY L.588, PG.871; FND 1/2" ROD; N20W 95.00' TAG
11192 IN T/P, N60E 37.48' NAIL & WASHER IN P/P, EAST 1.5' C/L RD, EAST 29.00' NAIL & TAG
11192 W. ROOT 10" MAPLE, N45W 16.50' 1/2" ROD AT EDGE PVMNT.

NOTE: THIS CORNER IS COMMON WITH M-12 T13N-R7E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD 1'W. OF C/L ASPH. ROAD N-S & ON FIELD
DIVISION LINE TO E. RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND ROD IS IN
SAME POSITION AS 1976 LCRC CITED ABOVE

ACCEPTED FND. 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-12 REPLACED FND ROD W/ STANDARD REMON MONUMENT STAMPED "M 12 T13N R7E" IN MON. BOX
N39°W, 16.59' FND. 1/2" ROD
N18°W, 95.32' FND. NAIL W/FLAG IN E. FACE T. POLE
EAST, 29.56' FND. NAIL W/FLAG. IN S. FACE 16" ELM
N71°E, 37.52' FND. NAIL W/FLAG. IN S. FACE P. POLE
N69°E, 93.83' SW CORNER OF HOUSE



Signed by Jonathan M. Field Date 11-6-96
Surveyor's Michigan License No. 37276

11-4-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

RECORDED

MAY 20 1997

CLERK

86



GILFORD ROAD

M-11

179°51'24"

A-11

1996 REI 2635.40'
1834 GLO 2640'

SEC. 36
T13N-R7E

M-12

180°06'24"

A-12

VASSAR ROAD

SEC. 31
T13N-R8E

1996 REI 2631.15'
1834 GLO 2640'

SEC. 36
T13N-R7E

L-13

179°59'22"

1984 LEDY 2640.40'
1996 REI 2641.49'
1834 GLO 2640'

M-13

89°48'46"

L-1
VAN GIESEN ROAD

M-1

90°01'20"

SEC. 1
T12N-R7E