

LAND CORNER RECORDATION CERTIFICATE

**Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. #774
FAIRGROVE TWP
95 NOV 15 PM 3:29
VIRGINIA H. HOLLAREN
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in FAIRGROVE TWP.
TUSCOLA (County) Located In: Corner Code #

1. Public Land Survey	T 13N R 08E	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 28 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 GLO; WAMPLER, D.S.; SET POST; BEECH 17 S67W 6 1/2LKS., BEECH 11 S57E 23LKS.
1905 BRUMLEY, C.S.; SURVEY OF SEC.34; C.P.; MAPLE 28 N29W 1.02 1/2, C.P. & TILE N45E 60LKS.
1991 ROWE ENG.; OWENS, P.S.#20709; SURVEY L.634 PG.1346-9; FND LARGE POINTED STONE, SMALLER STONES AND BROKEN CLAY TILE; CUT CHIS. + IN TOP OF STONE; NORTH 0.43' SET ROD W/CAP, WEST 0.30' SET ROD W/CAP, SOUTH 12.35' SET ROD W/CAP #20709, S65E 33.48' SET ROD W/CAP #20709, N50E 55.15' SET NAIL W/TAG #11192 IN P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995 ROWE ENG.; FIELD, P.S.#37276; FND. POINTED STONE W/ CHIS. + ON TOP 1'N. OF C/L GRAVEL ROAD E-W & 5'E. OF C/L ASPH. ROAD TO N.; RECOVERED 5 PREVIOUS WITS INDICATING THAT FND STONE IS IN SAME POSITION AS 1991 STONE CITED ABOVE

ACCEPTED FND. STONE AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 REPLACED FND STONE AND IRONS W/ STANDARD REMON MONUMENT STAMPED CAP G13 T13N R8E
SOUTH, 12.35' FND. 1/2" ROD W/CAP #20709
S65°E, 33.48' FND. 1/2" ROD W/CAP #20709
N50°E, 55.15' FND. NAIL W/TAG #11192 IN SE FACE P.POLE
N45°E, 29.76' SET CHIS. NOTCH IN TOP N. END 24" CMP
S50°E, 21.95' SET CHIS. NOTCH IN TOP S. END 24" CMP



Signed by Jonathan M. Field Date 11-15-95
Surveyor's Michigan License No. 37276


FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1993
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY & REMONUMENTATION

APPROVED
11-6-95
[Handwritten initials]

DEC 6 1995

COPY



SE 1/4
SEC 33
T13N-R8E

SW 1/4
SEC 34
T13N-R8E

