

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
1995 REMONUMENTATION PROGRAM

For corners in FAIRGROVE TWP.

TUSCOLA Located In: Corner Code #

1. Public Land Survey	T	13N	R	08E	L-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 28 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821 GLO; WAMPLER, D.S.; SET POST; SUGAR 16 S63E 11LKS., IRONWOOD (NO SIZE) S66W 1 1/2LKS.
- 1859 CRANSTON, C.S.; SURVEY OF SEC.36; NO OBJECT STATED; LYNN N81 1/2W 71LKS.
- 1972 KAY ENG.; KAY, P.S.#14096; SURVEY L.2 PG.150; NO OBJECT STATED; N40E 37.55' 36" STUMP, N75E 93.3' 18" MAPLE, N80E 137.6' 14" MAPLE
- 1979 QUIST, P.S.#25868; LCRC PG.40; SET 1/2" ROD BY SINGLE PROPORTION; WEST 33.00' N1/4 COR SEC.1 T12N-R9E, SOUTH 10' C/L GRAVEL ROAD, NE 73.66' RR SPIKE IN 18" MAPLE, WEST 14' OCC LINE TO SOUTH
- 1985 EMERY, P.S.#24593; SURVEY L.550 PG.777; FND 1/2" ROD; SAME WITS AS 1979 LCRC ABOVE; ALSO FND 3/8" ROD S49W 20.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1995 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD W/CAP #11192 AT N. EDGE OF GRAVEL ROAD E-W; RECOVERED 2 PREVIOUS WITS INDICATING THAT FND ROD IS IN SAME POSITION AS 1979 ROD CITED ABOVE

ACCEPTED FND ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 REPLACED FND ROD W/ STANDARD REMON MONUMENT STAMPED CAP L13 T13N R8E
- WEST, 33.01' FND. 1/2" ROD W/CAP #11192
- N70°E, 73.66' FND. RR SPIKE IN SW ROOT 24" MAPLE
- S15°E, 28.38' SET 1/2" ROD W/CAP #37276
- S70°W, 103.84' SET NAIL W/REMON TAG IN SE FACE 5" ELM
- N80°E, 119.86' SET NAIL W/REMON TAG IN S. FACE 20" MAPLE

RECEIVED FOR RECORD  
LIBERNO. \_\_\_\_\_ PAGE NO. \_\_\_\_\_  
FILING NO. 479  
FAIRGROVE TWP  
95 NOV 15 PM 3:31  
VIRGINIA H. McLAUREN  
TUSCOLA COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Jonathan M. Field  
Surveyor's Michigan License No. 37276

Date 11-15-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993



APPROVED  
11-6-95  
J.M.F.  
mg

DEC 6 1995  
COMMISSIONER

COPY

