

SURVEY & REMONUMENTATION

DEC 02 1993

COMMISSION

1993 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FAIRGROVE TOWNSHIP

For corners in

TUSCOLA

(County)

Located In:

Corner Code //

- | | | | | | |
|---------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 13N | R | 8E | M-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

RECEIVED FOR RECORD
 LIBER NO. _____ PAGE NO. 65
 FILING NO. Fairgrove Twp.
 93 NOV -2 PM 3:56
 VIRGINIA M. McLAUGHLIN
 TUSCOLA COUNTY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4		3		2					
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton, in a field survey on Aug. 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes	Nov., 1969 Witness card - source unknown
Joseph Wampler, D.S.	Set 3/4" rod in mon. box.
Set post corner Sec. 12 & 13	S45°E 44.85' t.p.
Birch 11" N54°W 9.24'	S05°E 89.20' 35" maple.
Lynn 14" S48°E 1.98'	N50°W 40.21' t.p.
	South 50.16' NW cor. Sec. 19
	North 2685.47' E 1/4 cor. Sec. 12.
	West 2652.48' N 1/4 cor. Sec. 13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted 5/8" brass rod in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 2" diameter brass cap over 5/8" brass rod and encased in concrete. Stamped brass cap, corner M-5, T13N-R8E.
 S00°10'10"W 49.91' apparent corner A-7, T13N-R9E. Found 1" iron rod.
 S05°01'W 21.83' found MDOT tag & p.k. nail in physical centerline N-S pavement.
 N59°22'W 40.09' set T.C. Re-mon. tag & spike over MDOT tag in NE face t.p. stub.
 N58°20'E 137.40' NW cor. footings of Bethel M.E. Church.
 N81°26'E 127.80' SW cor. of church tower.
 S89°51'E 88.90' found bolt in S. face of 40" maple, set T.C. Re-mon. tag & spike above bolt.

Signed by

[Signature]

Date

Oct. 25, 1993

Surveyor's Michigan License No. _____

23503

APPROVED
 10-25-93

[Signature]



