

SURVEY & REMONUMENTATION

DEC 02 1993

COMMUNICATION

1993 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COPY

RECEIVED FOR RECORD
LIBRARY NO. _____ PAGE NO. 4
FILING NO. Fairgrove Twp.
93 NOV -2 PM 3:56
VIRGINIA H. McLELLAN
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in
TUSCOLA
(County)

Located In: FAIRGROVE TOWNSHIP Corner Code: //

- 1. Public Land Survey T 13N R 8E M-6
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton, in a field survey on Aug. 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes	No date - witness card - source unknown.
Joseph Wampler, D.S.	Found part of wood stake 1.5' below?
Set 1/2 mile post.	No mention of object set.
Ash 9" N14°W 9.24'	S20°W 64.07' 23" maple.
Ash 20" N87 1/2°W 5.94'	West 31.07' fence post.
	N25°W 64.77' 17" elm.

Note: Section A. continued on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted 1 1/2" pipe in monument box per Act 74 of record.
S20°W 64' ± remains of 30" stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 2" diameter brass cap over 1 1/2" pipe and encased in concrete. Stamped brass cap, corner M-6, T13N-R8E.
South 83.51' found 1/2" re-rod on township line.
N87°30'W 33.75' set Re-mon. tag & spike over MDOT tag in S. face 6" wood post.
N30°51'E 113.53' set Re-mon. tag & spike over MDOT tag in SE face of p. pole.
N90°00'E 50.00' set 1/2" x 18" rod & cap #23503 on ditch bank.
S30°30'E 100.00' set 1/2" x 18" rod & cap #23503 on ditch bank.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date Oct. 25, 1993

APPROVED
10-25-93
[Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

Continued from Section A. on front of this form:

Feb. 14, 1984 Act 74, Fairgrove Township, Page 42 by Kay Don Fluke, R.L.S. #18988.

Found 1 1/2" pipe in monument box.

S30°W 64.07' maple 25"

N80°W 33.07' wood post.

N35°E 113.55' p.p.

3' East of centerline of Unionville Rd.

