

**SURVEY & REMONUMENTATION**  
**DEC 02 1993**  
**COMMISSION**

**1993 REMONUMENTATION PROGRAM**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**FAIRGROVE TOWNSHIP**

For corners in  
TUSCOLA  
(County)

Located In: Corner Code //

- |                                    |   |             |   |            |     |
|------------------------------------|---|-------------|---|------------|-----|
| 1. Public Land Survey              | T | <u>13</u> N | R | <u>8</u> E | M-7 |
|                                    | T |             | R |            |     |
|                                    | T |             | R |            |     |
|                                    | T |             | R |            |     |
| 2. Property Controlling in Section | S |             | T | R          |     |
|                                    | S |             | T | R          |     |
| 3. Miscellaneous Property in Sec.  | S |             | T | R          |     |
|                                    | S |             | T | R          |     |

RECEIVED FOR RECORD  
 FILING NO. 102 PAGE NO. 2  
 93 NOV -2 PM 3:56  
 VIRGINIA H. MERRILL FOR  
 TUSCOLA COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth D. Dunton in a field survey on Aug. 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes	Oct., 1969 Witness card - source unknown.
Joseph Wampler, D.S.	Found 3/4" pipe 1' below surface - raised
Set post cor. Sec. 13 & 24	with 1/2" pipe, set mon. box.
Birch 9" S80°W 9.90'	N65°E 46.64' p.p.
Sugar 20" N82 1/2°E 15.84'	S35°W 84.23' t.p.
	S75°W 85.00' t.p.

Note: Section A. continued on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted 1/2" rod in 1/2" pipe in monument box per survey & Act 74 of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 2" diameter brass cap over 1/2" rod & encased in concrete. Stamped brass cap, corner M-7, T13N-R8E.  
 South 79.15' found 1/2" I.D. pipe in mon. box on township line.  
 S24°24'W 83.10' set T.C. Re-mon. tag & spike over MDOT tag in E. face of t.p. stub.  
 N59°09'E 30.63' found "+" atop N. end 111' of 84" c.s.p. culvert.  
 S14°05'E 97.79' found "+" atop S. end 111' of 84" c.s.p. culvert.  
 N60°17'E 48.20' set T.C. Re-mon. tag & spike in NW face new p. pole.  
 S75°00'E 45.00' set 1/2" x 18" rod & cap #23503.

Signed by [Signature]  
 Surveyor's Michigan License No. 23503

Date Oct. 25, 1993

**APPROVED**  
10-25-93

[Signature]  
[Signature]

STATE OF MICHIGAN  
 KENNETH D. DUNTON  
 LAND SURVEYOR  
 Lic. 23503  
 LICENSED PROFESSIONAL SURVEYOR  
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983

Continued from Section A. on front of this form:

June 2, 1976 Survey Liber 462 - Page 911 by David T. Rowe, R.L.S. #11192. Found 1/2" pipe in mon. box - raised with 1/2" re-rod over pipe.

South 79.11' SW cor. Sec. 19, T13N-R9E.

N65°E 46.33' MSHD tag in p.p.

East 12.05' face of N. leg of sign.

S35°W 84.13' MSHD tag in t.p.

Feb. 14, 1984 Act 74, Fairgrove Township, Page 43 by Kay Don Fluke, R.L.S. #18988.

Found 3/4" pipe with R.L.S. cap (could not read number).

N65°E 46.64' p.p.

S10°E 97.80' cross on South end of CMP.

S30°W 84.00' telephone marker (wood post).

0.5' North of centerline of Fairgrove Rd. & 6' East of centerline of Unionville Rd.

