

COPY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: ALMER TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>09E</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 101
FILE NO. ALMER TWP.
97 OCT - 7 PM 3:04

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:
1835 GLO; PARKE, D.S.; SET POST; W.OAK 40 N17E 51LKS., BEECH 14 S21E 38LKS.
1980 HOOTH, LS#7966; LCRC PG.32; FND. AKERMAN PLUG SET BY MDSH IN 1969, REPLACED W/ 1/2" BAR (IN MON BOX); N03E 104.27' NE COR. SEC.36, N47E 100.72' SW COR PORCH, N60E 60.67' 16" ASH, S20E 65.08' P.POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1980 HOOTH LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND ROD AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1 REPLACED 1/2" ROD W/ 5/8" ROD & STANDARD REMON CAP STAMPED A 13 T14N R9E IN CONC. IN MON. BOX NORTH, 104.31' FND. TUSCOLA CO. MONUMENT AT M-11 T14N-R8E
N54°E, 60.88' NAIL W/TAG #37276 IN NW FACE 20" ASH (SET NAIL W/TAG)
S40°E, 73.41' P-K NAIL W/TAG #37276 IN SW FACE P.POLE (SET P-K NAIL W/ TAG)
S55°W, 34.74' 1/2 ROD W/CAP #37276 (SET ROD W/CAP)
N32°W, 58.18' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)
N44°E, 100.70' SW CORNER CONC. BLOCK FOUNDATION

NOTE: THIS CORNER IS COMMON WITH A-13 T14N-R9E

Signed by *Jonathan M. Field* Date 10-7-97
Surveyor's Michigan License No. 37276



APPROVED
10-6-97
[Signature]

SURVEY &
REMONUMENTATION

NOV 26 1997

COMMISSION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983



UNIONVILLE ROAD 104.32' REMON '93
104.31' REI '97
104.28' GLO
2479.43 REMON '93
2479.46 REI '97



M-11
T14N-R8E
1993 REMON. S.AKRON TWP. PG.69

SEC. 31
T14N-R9E

A-13 FND. 0.04' W. OF TWP. LINE AS MONUMENTED
189°29'45" B-13



1191.62' REI '97
1834 GLO 1191.30'

180°00'00"



90°28'55"

ELMWOOD ROAD

A-1

SEC. 6
T13N-R9E



M-12
T14N-R8E
1993 REMON. S.AKRON TWP. PG.68