

MAR 05 1998

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. #67

SECTION

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILE NO. ALMER TOWNSHIP
97 NOV -5 PM 4:00

For corners in Almer Township

Tuscola

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>13N</u> R <u>09E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

[Signature]
TUSCOLA COUNTY
REGISTERED SURVEYORS

COPY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on July 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Dec. 27, 1834, Hervey Parke, D.S. Set post corner Sections 32 & 33, Sugar 12" N64 1/2°E 86 links, Sugar 6" N64°W 12 links. June 5, 1973 L.C.R.C. Page 11 by Rowe, L.S. #11192, found iron ring. West 128.7' NW cor. Sec. 4, T12N-R9E, N20°E 27.1' \pm pole. March 10, 1992 L.C.R.C. Page 58 by Field, L.S. #37276. Fnd. 1" pipe; distance to NW cor. Sec. 4, T12N-R9E indicates it is in same position as iron ring. N73°W 181.84' set tag #11192 in S. face p. pole, S83°W 124.37' N. edge sign post, N01°E 32.01' fnd. tag #11192 E. face fen. post, East 128.17' fnd. R.R. spike @ NW cor. Sec. 4, T12N-R9E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod over 1" pipe on occupied fence line North. Found two accessories that indicate the rod & pipe found are in the same position as the 1992 L.C.R.C. Accepted rod & pipe found as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 5/8" rod and 1" pipe and placed concrete monument with standard brass cap stamped E-13, T13N-R9E. Placed monument box over monument. N73°W 182.28' set remon. tag & spike in S. face new p. pole. N02°E 53.37' set remon. tag & spike in W. face new p. pole. North 32.06' fnd. 11192 tag & nail in E. face 6" wood cor. post. East 128.24' fnd. 1" pipe @ apparent corner E-1, T12N-R9E.

Signed by [Signature]
Surveyor's Michigan License No. 23503

Date 10-20-

APPROVED
10-20-97

[Signatures]



