MAR 0 5 1998

## SECTION

\_, Recorded Plat

## 1997 REMONUMENTATION PROGRAM

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

for corners in Almer Township

4. Lot No.

5. Private Claims

Tuscola Located In: Comer Code # (County) 1. Public Land Survey F-13 2. Property Controlling in Section 3. Miscellaneous Property in Sec.

HER NO. PAGE NO. 468 THE NO. PAGE NO. 468 ALMER TOWNSHIP 97 NOV -5 PN 4:00
Grown Schiller
GOPY

Kenneth D. Dunton, in a field survey on July 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate,

1	A_	B	Ç	D	E	F	G	н	I	J	ĸ	LN
2		 -6-	$\perp$	 - 5-		- / ~		1		Ĭ	T	Ť
3	_	4_	ļ_	Ī.,	1_	L			1	1	1	1—
4	_	· 7	1	8-		8		-10-	T		1	
5	<u>_</u>	<u> </u>	_	L		Ľ		]	1		1	12
6	_	 18		<u> </u>	L	15	Γ					
7	L	Ĭ.		]				15	<del>                                     </del>	4	<del>  -1</del>	3—  
8 :	1	9	<u> </u>	<u> </u> 20—		21		22_		_	-	
ا و		_					$\prod$		2	<b>J-</b>	2	4
10	 3	 30	;	ا ا		8	Ī.,			_		
11		_							2: 	6— !	2!	5—
12		l	3	2	3	a _						
13	_	ل	Ĭ		Ĭ		-	"	3! 		36 	<u></u>

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

Dec. 27, 1834 Hervey Parke, D.S. Set quarter section post, Hemlock 8" N59 1/2°E 21 links, Birch 10" N58°W 36 links. May 10, 1979 L.C.R.C. Page 36 & survey L-498, P-1152 & 1153 by Quist, R.S. #25868, found 3/4" iron rod. East 110.10' R.R. spike w/ "+" @ N 1/4 cor. Sec. 4, T12N-R9E, S10°E 36.23' center 3" Maple, S35°W 54.32' 11192 tag 24" Maple, N45°W 44.78' 11192 tag 18" same as 1979 survey L-542, P-389 & 390 by Boldt, L.S. #28405, object and accessories North 33.00' fnd. 1 1/2" pipe, N54°W 44.77' fnd. nail & tag #11192 in SW face 20" Maple, N52°W 24" Maple, East 110.06' fnd. R.R. spike @ N 1/4 cor. Sec. 4, T12N-R9E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 3/4" rod. Found six accessories that indicate the iron rod found is in the same position as the iron rod found in 1979 & 1991. Accepted 3/4" iron rod found as the best evidence of the

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 3/4" iron rod and placed concrete monument with standard brass cap stamped F-13, T13N-R9E. Placed monument box over monument.

N53°40'W 88.30' fnd. 11192 tag & nail in NE face p. pole, set remon. tag over 11192 tag. S41°20'W 54.29' fnd. spike in NW face, 27" Maple, set remon. tag over spike. N55°40'W 44.41' set remon. tag & spike in SW face 18" Maple. S10°E 36.24' set remon. tag & spike in E. face 12" Maple. N00°44'W 32.94' fnd. 2" o.d. pipe flush with gravel surface. East 110.05' fnd. 3/4" iron rod at apparent cor. F-1, T12N-R9E.

Surveyor's Michigan License No. 23503

TE OF MICHIGAN KENNETH

DUNTON

APPROVED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROCESSION PREASED MAY
REVISED OX

HEHAL SURVEYORS, JAN. 28, 1971

Sec. 33 T13N-R9E 1834 Parke 2640' 1997 Dunton 2639.85' 1834 Parke 2640' 1997 Dunton 2640.09' E-13 G-13 -Township Line 110.10' 110.10' 110.06' 1979 Quist 1984 Boldt Apparent Cor. F-1, T12N-R9E 1991 Field 1997 Dunton 110.05 Sec. 4 T12N-R9E