

COPY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. 143
FILE NO. Almer Township
97 OCT -7 PM 3:04

TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in: ALMER TWP.

| | | |
|------------------------------------|---------------------------|---------------|
| <u>TUSCOLA</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>13N</u> R <u>09E</u> | <u>M-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 23 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1835 GLO; PARKE, D.S.; SET POST; HEMLOCK 10 N86E 20LKS., HEMLOCK 9 S77W 8LKS.
1886 TESKEY, C.S.; STAKE PREV. ESTABLISHED STAKE & STONE AT CORNER; STAKE N45E 70LKS., STAKE S45W 70LKS.

1980 ROWE; FOKENS, P.S.#21567; SURVEY L.508 PG.989; 1/2" ROD; N40W 49.80' TAG #11192 IN T.POLE, S50W 51.50' TAG #11192 IN FENCE POST, S35W 54.21' TAG #11192 IN FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 ROWE; FIELD, PS#37276; FND. 1" PIPE IN MON. BOX ; RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND. PIPE IS IN SAME POSITION AS 1980 ROWE SURVEY CITED IN SECTION A. ABOVE

ACCEPTED FND PIPE AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 SET 5/8" ROD & STD. REMON. CAP STAMPED M 13 T14N R9E INSIDE FND. PIPE, ENCASED IN CONC. IN MON. BOX
N40°E, 75.56' NAIL W/TAG #37276 IN NW FACE 10' COTTONWOOD (SET NAIL W/TAG)
N46°E, 46.34' SW FACE ROAD SIGN POST
S39°W, 33.08' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)
S42°E, 37.61' 1/2" ROD W/CAP #37276 (SET ROD W/CAP)
N38°W, 49.70' NAIL W/TAG #11192 IN SE FACE P.POLE (FND NAIL W/TAG)

NOTE: THIS CORNER IS COMMON WITH M-13 T14N-R9E, A-13 T14N-R10E, AND A-1 T13N-R10E

Signed by Jonathan M. Field Date 10-7-97
Surveyor's Michigan License No. 37276



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JUNE 28, 1975
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
10-6-97
[Signature]

SURVEY &
REMONUMENTATION

NOV 26 1997

COMMISSION

COPY

