

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: ELLINGTON TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>10E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 24 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1834 GLO; PARKE, D.S.; SET POST; HEMLOCK 16 N59E 20LKS., HEMLOCK 16 N56 1/2W 39LKS.
 1972 ROWE, P.S.#11192; LCRC PG.11; SET T-IRON AT C/L OF ROADS N-S-E-W; S05W 40.47' TAG #11192 IN P.POLE, S40E 62.66' TAG #11192 IN T.POLE, S10W 36.18' ROAD SIGN, N65E 75.15' TAG #11192 IN 12" COTTONWOOD
 1982 DUNTON SURVEYING; DUNTON, P.S.#23503; SURVEY L.527 PG.1477-1478; FND. T-IRON; SAME WITS AS 1972 LCRC ABOVE
 1992 ROWE; FIELD, P.S.#37276; SURVEY L.636 PG.886; FND. T-IRON; S05W 40.45' TAG #11192 IN P.POLE, S10W 36.30' C/L ROAD SIGN POST, N65E 74.98' P-K NAIL IN 30" COTTONWOOD, N45W 63.60' SW COR. 4X4 POST
 1992 ROWE; FIELD, P.S.#37276; SURVEY L.684 PG.1119-1120; FND. T-IRON; SAME WITS AS 1992 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 ROWE; FIELD, PS#37276; FND. T-IRON; RECOVERED 4 PREVIOUS WITNESSES WHICH INDICATE THAT FND. T-IRON IS IN SAME POSITION AS 1972 ROWE LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND. T-IRON AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED E 13 T13N R10E IN MON. BOX
 N59°E, 74.98' FND. P-K NAIL IN NW FACE COTTONWOOD
 N83°E, 33.33' FND. 1/2" ROD W/CAP #37276
 S53°E, 62.73' SET P-K NAIL W/TAG #37276 IN NE FACE CUT-OFF T.POLE
 S09°W, 40.45' FND. NAIL W/TAG #11192 IN E. FACE P.POLE
 S15°W, 36.30' CENTER OF ROAD SIGN POST
 N62°W, 82.28' SET NAIL W/TAG #37276 IN SW FACE TWIN 8" CHERRY



Signed by Jonathan M. Field Date 9-24-97
 Surveyor's Michigan License No. 37276

APPROVED
9-22-97
[Handwritten initials]

SURVEY &
 REMONUMENTATION

NOV 26 1997

COMMISSION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1983

