

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: **ELLINGTON TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>10E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 24 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET POST; B. ASH 7 N59E 12LKS., ELM 11 N56 1/2W 16LKS.
1977 CASE SURVEYING; CASE, P.S.#15399; SURVEY L.475 PG.338; FND. 1 1/4" PIPE; N35W 57.2' SPIKE IN 5" POST, S35E 26.18' S. END CMP, N35E 35.9' N. END CMP
1980 BOLDT, P.S.#28405; LCRC PG.33; FND. 1 1/4" PIPE; SAME WITS AS 1977 CASE SURVEY ABOVE
1992 ROWE, FIELD, P.S.#37276; SURVEY L.636 PG.886; FND. 1/2" IRON; S80E 86.75 C/L ROAD SIGN POST, S40W 9.55 E. SIGN POST LEG, S85W 21.50 P-K NAIL IN 20" ELM, N85E 57.60 C/L STOP SIGN POST
1992 ROWE, FIELD, P.S.#37276; SURVEY L.684 PG.1119-1120; FND. 1/2" ROD; SAME WITS AS 1992 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1992 ROWE SURVEY CITED IN SECTION A. ABOVE

ACCEPTED FND. ROD AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED G 13 T13N R10E
N82°E, 57.67' S. EDGE OF STOP SIGN POST
S65°E, 86.48' FND. NAIL W/FLAG. IN SW COR. 4X4 POST W/ PHONE RISER
S61°E, 84.59' CENTER OF ROAD SIGN POST
S15°E, 49.46' SET CHIS. NOTCH IN W. END 18" CMP
S71°W, 21.47' FND. P-K NAIL IN N. FACE 16" ELM
N35°W, 39.00' SET 1/2" ROD W/CAP #37276

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. # 43
ELLINGTON TOWNSHIP
97 OCT -7 PM 3:03
Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by *Jonathan M. Field* Date 9-24-97
Surveyor's Michigan License No. 37276



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
9-22-97
[Signature]

SURVEY &
REMONUMENTATION
NOV 26 1997
COMMISSION

