

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #47
ELLINGTON TOWNSHIP
97 OCT -7 PM 3:03
Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

For corners in: ELLINGTON TWP.

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>10E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 24 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET POST; HEMLOCK 12 N83E 10LKS., HEMLOCK 8 N59W 36LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD

ACCEPTED FND. ROD AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED K 13 T13N R10E
EAST, 80.86' FND. T-IRON APPARENT K-1 T12N-R10E
N64°W, 70.15' FND. NAIL W/FLAG IN TOP OF 4X4 POST
NORTH, 65.08' SET NAIL W/TAG #37276 IN W. FACE 6" POPLAR
S46°E, 44.17' SET 1/2 ROD W/CAP #37276
S35°W, 60.12' SET NAIL W/TAG #37276 IN SE FACE 10" POPLAR
S74°E, 112.32' FND. U.S.G.S. BENCHMARK "PTS 67 W 1919"



Signed by *Jonathan M. Field* Date 9-24-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

APPROVED
9-22-97

*1400
JPE
RJB*

SURVEY &
REMONUMENTATION

NOV 26 1997

COMMISSION

