

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: **ELLINGTON TWP.**

<u>TUSCOLA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>10E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 24 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; PARKE, D.S.; SET 1/4 SEC. POST; PINE 24 N32W 4 1/2LKS., HEMLOCK 20 N80E 17LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 3/4" ROD

ACCEPTED FND. ROD AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-13 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED L 13 T13N R10E
N87°E, 140.79' SET 1/2" ROD W/CAP #37276
S62°E, 70.30' SET NAIL W/TAG #37276 IN NE FACE 32" OAK
S38°E, 45.96' SET P-K NAIL W/TAG #37276 IN SW FACE T.POLE
N45°E, 41.55' FND. NAIL W/FLAG. IN NW FACE P.POLE
NORTH, 33.74' FND. NAIL W/FLAG. IN W. FACE FENCE COR. POST
S53°W, 59.92' SET NAIL W/TAG #37276 IN NW FACE 12" PINE

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILE NO. #48
ELLINGTON TOWNSHIP
97 OCT -7 PM 3:03
Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2				
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

Signed by *Jonathan M. Field* Date 9-24-97
Surveyor's Michigan License No. 37276



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1975
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
9-22-97
JMB
RRB

SURVEY &
REMONUMENTATION
NOV 26 1997
COMMISSION

