

COPY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
BOOK NO. _____ PAGE NO. _____
FILE NO. #51
ELLINGTON TWP TOWNSHIP
97 OCT -9 PM 1:07

For corners in: ELLINGTON TWP.

TUSCOLA (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>10E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jonathan M. Field
TUSCOLA COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JULY 25 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1835 GLO; PARKE, D.S.; SET POST; HEMLOCK 28 N1W 32LKS., HEMLOCK 12 S14W 9LKS.
1987 HURON SURVEYING; BROWN, P.S.#24588; SURVEY L.572 PG.330; FND. 1/2" ROD; N45E 81.0' R.R. SPIKE IN P.POLE, S45E 84.34' SW COR. CONC. GARAGE, S60E 68.93' NW COR. CONC. GARAGE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, P.S.#37276; FND. 1/2" ROD; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. 1/2" ROD IS IN SAME POSITION AS 1987 SURVEY CITED IN SECTION A ABOVE; ALSO FND. FRAGMENTS OF WOOD BELOW FND. 1/2" ROD

ACCEPTED FND. ROD AS BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-1 REPLACED FND. ROD W/ STD. REMON. MONUMENT STAMPED M 13 T14N R10E
N40°W, 61.90' SET NAIL W/TAG #37276 IN NE FACE 6" ELM
N46°E, 80.83' FND. NAIL W/TAG #11192 IN SE FACE P.POLE
S59°E, 68.89' NW CORNER CONC. BLOCK BLDG.
S54°W, 58.79' SET P-K NAIL IN NW FACE CUT-OFF T.POLE
S45°E, 84.31' SW CORNER CONC. BLOCK BLDG.



NOTE: THIS CORNER IS COMMON WITH M-13 T14N-R10E, A-13 T14N-R11E, AND A-1 T13N-R11E

Signed by Jonathan M. Field Date 10-7-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, 1971

REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

APPROVED
10-6-97
[Signature]

SURVEYOR
REMONUMENTATION

NOV 26 1997

COMMISSION

